

SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1905, by Munn & Co.]

Vol. XCII.—No. 8.
ESTABLISHED 1845.

NEW YORK, FEBRUARY 25, 1905.

RECEIVED
OFFICE Chief of Staff
No. _____
FEB 24 1905
MILITARY
INFORMATION DIVISION
CENTS A COPY
\$3.00 A YEAR.




Photo. by Hollinger.

[See page 162.]

Kelvin

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO., - - Editors and Proprietors

Published Weekly at
No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year for the United States, Canada, or Mexico, \$3.00
 One copy, one year, to any foreign country, postage prepaid, 20 lbs. 5d. 4.00
 THE SCIENTIFIC AMERICAN PUBLICATIONS.
 Scientific American (Established 1845) \$3.00 a year
 Scientific American Supplement (Established 1876) 3.00 "
 Scientific American Building Monthly (Established 1889) 2.50 "
 Scientific American Export Edition (Established 1879) 3.00 "
 The combined subscription rates and rates to foreign countries will be furnished upon application.
 Remit by postal or express money order, or by bank draft or check.
 MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, FEBRUARY 25, 1905.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

TURBINES FOR TRAMP STEAMERS.

The subject of the unsuitability of the turbine as a drive for ships of slow speed, that is, of speeds of about 9 or 10 knots an hour, at which the average tramp steamer travels, was recently discussed in the course of his presidential address before the Institute of Marine Engineers, by the Hon. C. A. Parsons, the man who, better than anyone else, is qualified to speak on this subject. The problem of turbine propulsion of ships at low speed presents the following dilemma: In a slow vessel the revolutions must be low, because a certain disk area and a certain blade area are necessary in the propeller if we are to avoid too great a slip ratio; but the pitch ratio cannot be reduced much below 0.8 without incurring excessive skin friction of the blades. This makes it necessary to use the highest revolutions possible under the circumstances, and these, in a 10-knot vessel, are necessarily very low. On the other hand, a certain surface speed of the turbine blades and a certain number of rows of blades are necessary to obtain a reasonable economy from a turbine; and if the revolutions are low, the diameter, and the number of rows must be increased. The result is that, for a speed of 10 knots, the diameter and the number of rows become inordinately great; the weight and the cost become excessive; and, of course, the efficiency of the turbine is somewhat impaired by the use of such extravagant dimensions in proportion to the power realized.

It will be news to the marine engineering world, and extremely interesting news at that, that Mr. Parsons says there is a way out of the difficulty, by which there can be obtained in a low-speed turbine the full measure of expansion essential to economy—an economy better than that of the best set of tramp engines of which he knows. He has found it possible to build a turbine that will operate economically under very low-pressure steam, even when it is running under slow revolutions. He states that the engines of a tramp steamer expand the steam down to about 7 pounds absolute pressure, when it is discharged to the condenser. The remaining energy, represented between the pressure of 7 pounds and that of say 1½ pounds, is practically lost. The new type of turbine is able to save about 70 per cent of this wasted energy; and the additional power due to the use of this low-pressure turbine is estimated at between 15 and 20 per cent of the whole power now realized—a gain which Mr. Parsons likens to that which was obtained in the advance from the compound to the simple reciprocating engine.

In referring to the possibility of the marine gas or oil engine becoming the extensive competitor of the steam engine, Mr. Parsons holds the same view which we have frequently expressed in this journal, that although such engines have realized a horse-power on a consumption from half to two-thirds of that of the best condensing steam engine, "it cannot yet be said that they can generally subsist on ordinary bunker coal. If, in the future, some form of gas producer using ordinary coal is successfully applied for use on board ship, and if the mechanical details of reversing can be satisfactorily arranged, then the steam engine or steam turbine will have to give place to the gas engine." That is exactly where we stand to-day, and as soon as our inventors and engineers can build a gas-producer that can take the ordinary "run of the mine," the application of the gas engine will become general in almost every branch of engineering. We do not know of a field of investigation or invention that holds out a richer prize than this.

THREE MONTHS OF RAILROAD SLAUGHTER.

The death roll of the railroads of this country continues to lengthen, and the number of casualties in any given period steadily increases. Accident Bulletin No. 13 of the Interstate Commerce Commission tells us that the number of persons killed in train accidents during the months of July, August, and September last year, as shown in reports made by the railroad companies to the commission, was 411, and that the number of injured was 3,747. Accidents of other kinds,

including those sustained by employees while at work and by passengers in getting on and off cars, etc., brought the total number of casualties for that quarter of the year up to 14,239, of which 1,032 were killed, and 13,207 were injured. These figures mean that in the course of a single year, were this rate of maiming and killing sustained, our railroad system would be directly or indirectly accountable for the death of 4,128, and the more or less serious injury of 52,828 people. The Bulletin of the Commission says that the quarter under review may, as a whole, be termed the most disastrous on record. Of the 228 passengers and 183 employees killed in train accidents, 217 cases are accounted for by six accidents, and these 217 were nearly all passengers. In one case of derailment, 88 people were killed. In one collision 63 were killed; in another, 24; and two other collisions accounted respectively for 18 and 16 deaths.

The true measure of the blameworthiness of the railroad systems, in this matter of injury and death, is not so much the total number of victims as it is the total number of accidents. There is no strict relation between the number of people killed in a particular accident and the amount of carelessness, or poor management, or neglect, that brought about that particular accident. A very slight defect, not easily detected, might result in the killing of a hundred people, whereas some glaring instance of neglect might cause an accident in which the casualties were extremely small. Therefore, the true test of the ability of our railroads to take proper care of the passengers who commit themselves to their care, is the list showing the total number of accidents in a given period, and more particularly the total number of collisions and derailments, the one indicating faults of operation, and the other faults of construction and upkeep. Tested even on this basis, the records of these three months are very damaging to the reputation of our railroad systems. For the three months there were 1,439 collisions and 1,321 derailments, of which 232 collisions and 137 derailments affected passenger trains.

The technical journals which are devoted particularly to the affairs of the railroads, have complained of such reiterated and bald statements of the totals in the Accident Bulletins, as we have been in the habit of presenting in the columns of the SCIENTIFIC AMERICAN. It is claimed that careful analysis of these returns would show that the condition of affairs is not nearly so bad as the simple statement of these figures would seem to imply. It is further objected that the frequent reference we have made to the fact that in a recent year the railroads of Great Britain were operated without the loss of the life of a single passenger is also misleading, for the reason that while it may be literally true, there are unrecorded considerations which considerably mitigate the force of the comparison. We have carefully read these articles, with an honest endeavor to see the drift of the arguments set forth; but we have to confess that we have found nothing to lessen the significance of the fact that, while we have been killing people at a rate which has risen for one quarter to over 4,000 a year, a great railroad system in another country, on which the traffic is far more dense, and therefore more difficult to handle than ours, was actually able to prosecute that traffic, day in and day out, without the loss of a single passenger.

There are several conditions peculiar to American railroads which account for our large casualty list. The chief among these, undoubtedly, is the inherent restlessness of a not inconsiderable section of our railroad employees, which shows itself in the chronic disposition to move on and try some new field of work. This results in a continual change of the personnel, with the result that at any given time, on any given road, there will be found a large number of employees who are entirely new to, or but little familiar with, the special local conditions surrounding their work. Now, it is this familiarity with the local conditions, over and above the general knowledge which any engineer, conductor, brakeman, signalman, switchman, must have of his duties in the abstract—it is this familiarity we say, that is the very best safeguard against railroad accidents, or at least against those that have to do with the running of the trains.

Second only in importance as a contributory cause to railroad accidents is the continual change which is taking place in the management and official staff of our railroads, and in their ownership. As a result of the mad whirl of organization and reorganization, combinations, receiverships, and what not, there is a continual change of management from president to roadmaster. Well-established organizations and systems of management, that have gained that smoothness and accuracy of working and that mutual confidence and sense of interdependence, which can only come from long and successful association in the operation of a particular system, are suddenly broken up by the sale of the road or its combination with some other system; new men are introduced into high offices; and they, in turn, have their own particular friends or well-trying assistants whom they naturally wish to introduce; heartburnings, jealousies, and disappointments ensue; and

the whole operative system of the road is shaken from summit to foundation; for the general unrest invariably distributes itself throughout the whole working force of the road, with a consequent lowering of discipline and more or less careless performance of duties.

If the time shall ever come when the various railroads will be content to recognize each other's spheres of influence and control; if a day is ever reached when this perpetual reorganization, this turning upside down of railroad management, shall cease, we may look for a return of that sense of stability and permanence which formerly made the average period of employment by any particular company much longer than it is to-day. Then, only, will there be a return of that personal interest and pride in one's work, and that sense of security as regards the permanence of one's job, which will do more than anything else to promote careful work, whether in the construction, the maintenance, or the operation of our steam railroads. Then, and not till then, shall we see a diminution in the disgraceful record of deaths and injuries which appears with painful regularity in the reports of the Interstate Commerce Commission.

FUTURE WATER SUPPLY OF NEW YORK CITY.

If anyone doubt the possibility of New York city's having to face a water famine within the next two or three years, he should read the report recently made to the Mayor of this city by the Commission on Additional Water Supply, from which he will learn that the average rate of consumption of Croton water during the past year has exceeded the amount which all of the present reservoirs in the Croton watershed, together with the great reservoir now being formed above the new Croton dam, can supply in a year of small rainfall. This emergency has been obscured by the fact that the rainfall and stream flow for the past two or three years have been larger than the average, as shown by the records of the Croton reservoir flow, which have been carefully kept for many years. No one can predict the year of the next severe drought; but the facts that the rainfall has been above the average for the past few years, and that periods of large and small rainfall follow in cycles, make it very likely that we shall have to face some years of small rainfall in the near future. Emergency work is being done in the Croton watershed by the construction, which is immediately to be undertaken, of two dams above the new Croton dam, which together will impound an additional twenty billion gallons, to be held in reserve against a dry season; but it will take at least two years and probably longer to complete these. That we are running perilously close to the margin is shown by the following figures: During the quarter ending September 30, 1904, the average daily use of water from the Croton basin was 290 million gallons, whereas the records show that the average annual daily fall of the Croton River fell to 209 million gallons in 1880, and to 222 million gallons in 1883.

Admitting then, as we must, that it is necessary at once, and with all speed, to provide additional water supply, the question becomes one of where to get it, how to store it, and how best to conduct it to the city. These are questions of engineering pure and simple, and as such they should be judged and determined. But, alas! there has fallen upon this problem, as upon every other big engineering question affecting the interests of this city, the pernicious blight of politics. The problem is so vast, it involves such big expenditures of money, such possibilities of patronage, to say nothing of "graft," that the political harpy is watching it with a hungry eye. The Ramapo scandal is fresh in the public memory; but the snake though scotched is not yet killed. The air is full of propositions, from Engineer Birdsall's \$90,000,000 tunnel aqueduct to the ex-governor's bill for State control of water rights. Meanwhile, the population of New York is growing by leaps and bounds, water consumption is increasing, and nothing is being done to adequately meet the crisis.

The agitation of this question is much older than the general public might suppose; for as far back as the year 1886, a study of the problem was made by Mr. R. D. A. Parrott, who pointed out the advantages presented by the Esopus and Schoharie creeks as a future source of water supply for this city. The results of his investigation were published in the SCIENTIFIC AMERICAN SUPPLEMENT of September 4, 1886; and it is an interesting fact that the scheme outlined at that time is practically identical, as far as the location of the reservoirs is concerned, with the Ashokan reservoir suggested by Mr. Birdsall, the present Acting Chief Engineer of the Department of Water Supply, Gas, and Electricity, and indorsed, after very considerable modifications, by the Burr-Freeman Commission in the report above referred to.

The report of the Chief Engineer calls for the construction of a dam across Esopus Creek, near Olive Bridge, and of a deep-tunnel aqueduct, 97 miles in length, from the dam to New York city. The magnitude of this part of the work will be realized more clearly when we bear in mind that the total length of

deep-tunnel construction of the present new Croton aqueduct is 29.85 miles, or less than one-third that called for in the Chief Engineer's plans. In detail, the plan proposed is to construct a single deep tunnel from Astoria, under the East River, to a point in Morrisania, whence there would be two deep tunnels to Rye Pond in the Bronx basin, a distance of 23 miles from Astoria, the two tunnels to be each 10 feet 6 inches circular aqueducts. Rye Pond reservoir, when full, would be 355 feet above mean tide. From this reservoir the plan calls for a single deep-tunnel aqueduct, 12 feet in diameter, extending by way of the east branch reservoir in the Croton basin to a point west of North Paterson, and thence due west to the Hudson River, and northwesterly to the Olive Bridge dam on Esopus Creek, which would have an elevation above mean tide of 555 feet. This 97 miles of deep aqueduct tunnel is expected to deliver 300 million gallons of water per day at an elevation of 300 feet above sea level at the Rye Pond reservoir to the north of the city limits, from which it would be led to Astoria as explained above. The cost of this deep tunnel is estimated at \$500,000 per mile, and the total cost of the completed work would be over \$90,000,000.

This briefly describes the first instalment of the future additional water supply. The report contemplates the construction of another aqueduct of equal capacity and probably greater length, which is to be constructed subsequently whenever it may be needed, to deliver 300,000,000 gallons of water from Catskill River at the same elevation at the city limit. The report further proposes that ultimately a third aqueduct of about the same length as the latter would be constructed, and draw yet another 300 million gallons a day from the lower waters of both the Catskill and Esopus creeks, this water to be delivered into Jerome Park reservoir. Although no estimate of the cost of the two latter additions is given, they may be presumed to equal that of the first reservoir and aqueduct; in which case the ultimate cost of the three aqueducts and reservoirs may be set down as about \$275,000,000. For this sum a total of 900,000,000 gallons per day, it is estimated, could be furnished from these regions. This is about three times the present consumption of New York city.

The Burr-Freeman Commission reports to the Mayor that it concurs with Mr. Birdsall in the opinion that the waters of Esopus Creek are exceptionally pure and soft, and constitute an almost ideal source for public supply. They consider that the storage volume of the Ashokan reservoir would reach 66 billion gallons, which is more than double the addition which has been made to our present supply by the construction of the new Croton dam. Strong objection is made to the construction of a 97-mile deep-tunnel aqueduct. It is true that this method was adopted, in the case of the new Croton aqueduct, in order to render it safe against destruction by malicious persons or by a public enemy; but it is held that considerations of this character have lost their force at the present time, as the introduction of a small quantity of high explosive through a shaft, or otherwise, might easily damage a deep tunnel so that, because of its inaccessibility, its repair might be a question of many months. For this reason, and because it may be so much more quickly and easily constructed, the Burr-Freeman Commission recommends a surface aqueduct, built by the cut-and-cover method. The accessibility of such an aqueduct renders repairs easily and quickly made; moreover, as years of experience have shown, the liability to malicious injury is very remote. The capacity of the proposed deep tunnel is 300,000,000 gallons per day; but the conveniences for cleaning and repairs are such to-day that there is no reason, in the opinion of the Commission, why the cut-and-cover aqueduct should not be built, if so required, to have a capacity of 500,000,000 gallons per day.

The Commission is further of the opinion that it is not desirable to build a tunnel costing four or five million dollars, for the purpose of leading the water of Schoharie Creek into the new reservoir, but prefers instead to construct a pipe line from a dam built on Condout Creek, and bringing an additional supply from that stream. Furthermore, instead of taking the water from a point at the center of the proposed Ashokan reservoir, the Commission would take the water from the lower end of the reservoir, so as to permit of a thorough circulation, and would build a cut-and-cover aqueduct to a reservoir known as the Hill View reservoir, located on the high ground between Yonkers and Mt. Vernon. The total length of this aqueduct would be 81 miles, a saving of 10 miles over the Birdsall line. The aqueduct proposed by the Commission would, however, connect with the new aqueduct at the Croton reservoir; and as the present total aqueduct capacity between Croton Lake and New York city is at least 75,000,000 gallons daily greater than the safe yield of the Croton watershed, including its proposed additional reservoirs, it would be necessary to build the Ashokan aqueduct for the present only as far as the Croton reservoir, and utilize the existing aqueducts, from that point to the city, to their full capacity. By adopting this plan it would be necessary to construct

at once only 58 miles of aqueduct, comprising about 18 miles of steel tube, 5 miles of tunnel, and 35 miles of cut-and-cover aqueduct. After a careful review of precedents and circumstances, the Commission estimates that this work could be constructed in not less than from five to eight years, according to the conditions encountered.

As matters now stand, the Mayor is seeking the needed legislative authority at Albany for pushing through the scheme as outlined by his Commission. Meanwhile the late Governor, Mr. Odell, professes to have discovered that it will be to the interests of all concerned if the question of water supply were placed entirely in the hands of the State; and so this most vital of all questions affecting the health, and we might say the very existence of the people of New York city, must needs wait, for the present at least, upon the exigencies of party politics.

THE HEATON AIRSHIP FAILURE.

BY ENOS BROWN.

Heaton's airship, the "California Messenger," was driven into San Francisco Bay February 12. The aeronaut had a narrow escape from drowning. When the airship was taken out for a trial on the morning of February 12 across the bay in Oakland, it was cold but clear and there was a slight north wind. This wind increased rapidly, however, and when the airship was fairly well up it appeared to strike a current of air of great velocity, for despite the rudder it was driven rapidly toward the bay. The aeronaut tried to steer it south of Oakland, but the airship was driven steadily across the mud flats and then over the bay.

The wind had created a heavy sea and the airship began to sink, so that the aeronaut was in a dangerous position. Apparently some gas escaped from the compartments at one end of the machine, and as the ship sank, one end went down while the other, fully distended, stood nearly perpendicular above the waves. The aeronaut's predicament was seen by several yachts, which at once went to his rescue. He was taken off, and the airship was towed back to Oakland.

The Heaton airship consists first of a silk gas reservoir 76 feet long and 14 feet in diameter, with a capacity of 10,000 cubic feet of hydrogen gas, of a lifting power of 600 pounds. Directly beneath the bag is a sheet of canvas, denominated by the inventor an "aeroplane," designed to assist the movement of the airship in falling or ascending. The rudder is lightly constructed of bamboo covered with sacking, and is governed by ropes at the will of the engineer, the air current, generated by the rapid revolution of engine and propeller, assisting in the prompt control of the airship in the line of direction as the operator determines. The platform upon which the operator stands is built of bamboo rods trussed to the net above by linen lines.

The engine is a marvel of design and lightness in construction. Though generating 20 horse-power, the weight, exclusive of propeller, is but 55 pounds. It is described as a double-cylinder, 4 by 4, revolving around a stationary crankshaft, the propeller blades being attached to and a part of said cylinders. It is constructed of steel, and the motive power is furnished by gasoline. Power is increased by the elimination of flywheels, as well as lightness by dispensing with water coolers, the cylinders being kept cool by the strong air currents generated by the rapid motion in revolving. The two fans have each a surface of 8 square feet, and are 5 feet from tip to tip.

THE MOORE-HESKETT DIRECT PROCESS FOR THE MANUFACTURE OF WROUGHT IRON AND STEEL.

The Moore-Heskett process, of which mention has already been made in these columns, is designed for the treatment of iron sands, or pulverized concentrated iron ore in a fine state of division.

The apparatus consists of an upper and a lower brick-lined revolving cylinder attached to a gas furnace. The cylinders are lined with fire bricks, and have several brick shelves running along their whole length. They are placed at an angle of about 10 per cent from the horizontal, and revolve slowly. The finely-divided ore is automatically fed into the upper cylinder, and is continuously being lifted up by the shelves, and made to fall in a fine spray as it travels to the lower end. The inside of the cylinder is maintained at a low red heat by waste gases passing through it from the gas furnace to the chimney. The heated particles of ore, as they are delivered from the lower end of the upper cylinder, fall into a lower cylinder through a vertical flue, and are delivered into the upper end of the lower cylinder at a red heat. The lower cylinder is connected at its upper end to a gas producer or retort, and is the channel through which the reducing gas is delivered to the gas furnace. The vertical flue between the two cylinders is so arranged that the sand can enter the lower cylinder, but the gases cannot enter the upper cylinder. As the fine red-hot particles of ore travel through the lower cylinder, they are constantly being lifted up

and made to fall through the reducing gases in the same way as in the upper cylinder, and are delivered at the lower end in a continuous stream, falling into the bath of the gas furnace below, where the deoxidized sand is melted as fast as it accumulates.

The gas furnace both for steel and wrought iron is made to revolve, and digest and deliver its product automatically.

The essential feature of the process is that iron ore in a finely-pulverized state is heated, deoxidized, and melted particle by particle, which enables the various operations to be carried on rapidly and continuously in one furnace, without loss of heat, and requiring practically no labor. The whole process can be carried out automatically from the ore to the fluid steel. Each separate particle of ore is made to fall a great number of times through the heating and deoxidizing atmosphere, kept at a suitable temperature below its fusing point. Under these conditions heating and deoxidation take place in a few minutes. The reduced ore then falls directly into a bath of molten metal, which is maintained at a very high temperature. As the reduced ore is gradually and constantly falling into the bath, and at a red heat itself, it is not difficult to keep up the temperature of the furnace and bath with a minimum of fuel.

The revolving cylinders of the feeding apparatus may be stopped at any time, in order to add any alloy and test samples before tapping.

In working, only a proportion, say half, of the metal is tapped out at any time, the bath being maintained constantly.

The hearth is lined with the most refractory basic material known, and should last for many months.

An excess of gas is passed through the deoxidizing cylinder; the balance not taken up by the iron ore follows the reduced ore into the furnace, and being highly combustible combines with the heated air. This arrangement insures thorough deoxidation in the cylinder and also prevents any possibility of reoxidation taking place, as the gas passes over the reduced ore in the bath, before combustion takes place, and effectually prevents any waste of gas, as complete combustion is obtained in the furnace, and the resulting products pass into regenerators for heating the air and afterward the ore-heating revolving cylinder.

THE CURRENT SUPPLEMENT.

Emile Guarini opens the current SUPPLEMENT, No. 1521, with an article on wireless telegraphy experiments at the Eiffel tower. Some interesting statistics are given of telephones and telegraphs in the United States. Mr. Frank Koester gives some practical data on European practice with steam turbines. The ore concentration plant exhibited at St. Louis, which has already been made the subject of some discussion in the SUPPLEMENT, is described in full. Mr. Philip Bjorling writes on pumps—machines that are much neglected. The Matitsch lace-making machine, a combination of the bobbinette and the English twist-lace machine, is fully described and illustrated. Sir John Eliot writes on meteorology in the British empire. Mr. J. A. Formoy recently lectured most instructively before the English Camera Club on "Suns: Their Various Stages of Development as Revealed by the Spectroscope." His lecture is abstracted. Prof. N. Monroe Hopkins presents his seventh paper on "Experimental Electrochemistry." The subjects treated in this installment are the following: Energy Required in Electrolysis, Practical Formula for Computing, Electrolytic Separation of Metals, the Rotating Anode in Electro-Analysis.

EXPLOSION OF A SUBMARINE.

On February 16 an explosion occurred on board the British submarine torpedo boat A5, resulting in the death of the commander and two of the crew and the disabling of fifteen men. From all accounts, it seems that the crew was engaged in filling the liquid fuel tanks of the vessel, and that the vapors from the gasoline became ignited. The explosion was terrific. Men were hurled in every direction, nine being afterward picked out of the water. A rescuing party sent from a nearby gunboat had hardly reached the scene of the accident when a second explosion occurred, which resulted in the injury of some of the rescuers. The submarine caught fire internally. When docked soon after, she was found to be not materially damaged.

THE CHARCOT ANTARCTIC EXPEDITION.

Much concern is felt for the fate of Dr. Charcot, who is leading an Antarctic expedition, which started more than a year ago.

It is known to have encountered a terrible storm in April last year and has not been heard of since, nor have any traces of its movements been discovered by Uruguay, which sent out a party to its rescue. M. Charles Rabot, a member of the committee of the Society of Geography of Paris, intends to organize another search party to ascertain its fate.

Dr. Charcot is the son of the famous nerve specialist, who was chief physician at the Salpêtrière Hospital.

HOW TO MAKE A MERCURY THERMOMETER.

The first thing to be considered in the making of a thermometer is the character of the glass to be used. The thermometer maker always selects a length of annealed glass, so hard that it melts with readiness only in the blowpipe, and absolutely uniform in bore. The length of glass is held in the blowpipe at the point where it is to be severed until it becomes so thoroughly plastic in the flame that it almost drops apart. When the glass has been thus softened it is withdrawn from the flame, grasped at each end, and quickly pulled apart. The result is two tubes, sealed at one end.

The next step is the formation of the bulb. One of the two tubes obtained by the process just described is held in the blowpipe, the sealed end being subjected to the heat. When the glass has been melted sufficiently, the tube is removed from the blowpipe. By blowing through the open end, a bulb of any size can be formed.

After the bulb has been blown, the next step is the filling of the tube with mercury. To effect this, the open end is plunged in a vessel of mercury. The liquid metal rises slightly in the tube. The tube is then reversed, so that the mercury runs down into the bulb. By heating the bulb in an alcohol flame or Bunsen burner, the mercury is made to boil. The vapors given off drive out the air, thereby creating a vacuum. When this point has been reached, the open end of the tube is plunged into mercury, which in order to fill the vacuum, rushes up and completely fills the tube. The open end is now closed with sealing


wax in order to prevent the entrance of air. Hermetic sealing is effected by holding the tube in the blowpipe beyond the wax-plugged open end, by drawing the molten end off.

Two fixed points must now be taken. The lower is


point. To determine this the tube of mercury is held in the steam of boiling water, which can be done by running the tube through a cork and suspending it by a wire or other means in the vapor. As the boiling point depends upon the pressure of the atmosphere, the height of the barometer must now be taken. If it stands at 760 millimeters, the temperature is 100 deg. C. If not, a calculation will be necessary; 1 deg. C. or 1.71 deg. F. must be added or subtracted for every 26.7 millimeters above or below 760 millimeters. The interval between the two fixed points is then divided into 100 parts or degrees for a Centigrade, or 212 parts for a Fahrenheit thermometer. To graduate the scale above 100 deg. a column of mercury is measured below that point, then made to pass above step by step; the portions of the tube filled by the column are then divided into the number of degrees which it represents.

A thermometer made in the manner described is not an absolutely scientific heat-recording instrument. Still, it will be found sufficiently accurate for use in ordinary life.

A thermometer made in the manner described is not an absolutely scientific heat-recording instrument. Still, it will be found sufficiently accurate for use in ordinary life.



Melting the Glass and Drawing It Apart.




Heating the End Before Blowing.



After the End Has Been Heated in the Blowpipe the Bulb is Blown.



Creating a Vacuum by Boiling Mercury in the Bulb.



Immersing the Tube in Mercury so That the Metal Rushes Up to Fill the Vacuum.

HOW TO MAKE A MERCURY THERMOMETER.

usually taken first. The thermometer is placed vertically in finely-pounded melting ice, or preferably snow, contained in a vessel which will allow the water to drain away. The whole of the mercurial column should be immersed in the ice. After from twenty minutes to half an hour the thermometer may be raised until the top of the mercury is seen just sufficiently for its position to be noted. This is the freezing point—32 deg. on the Fahrenheit thermometer, 0 deg. on the Centigrade.

The temperature of water boiling is the higher fixed


point. To determine this the tube of mercury is held in the steam of boiling water, which can be done by running the tube through a cork and suspending it by a wire or other means in the vapor. As the boiling point depends upon the pressure of the atmosphere, the height of the barometer must now be taken. If it stands at 760 millimeters, the temperature is 100 deg. C. If not, a calculation will be necessary; 1 deg. C. or 1.71 deg. F. must be added or subtracted for every 26.7 millimeters above or below 760 millimeters. The interval between the two fixed points is then divided into 100 parts or degrees for a Centigrade, or 212 parts for a Fahrenheit thermometer. To graduate the scale above 100 deg. a column of mercury is measured below that point, then made to pass above step by step; the portions of the tube filled by the column are then divided into the number of degrees which it represents.

A TACHOMETRIC WATCH FOR BICYCLES AND OTHER VEHICLES.

BY EMILE GUARINI.

The principle of the tachometric watch, illustrated herewith, is very interesting and very simple. It consists in causing the case of a watch to be revolved by the wheel of a vehicle in a direction contrary to that of the hand of the watch and at the same rate of speed.


(Continued on page 162.)



Tachometer Attached to Steering Head Below the Top Bar of Frame.



View Showing the Complete Apparatus Applied to a Bicycle.



Tachometric Watch Shown Mounted Upon the Post of Handle-Bar.

A TACHOMETER FOR SHOWING THE SPEED OF VEHICLES.

A BLAST OF DYNAMITE AND HOW IT WAS PHOTOGRAPHED.

BY ARTHUR INKERSLEY.

Though giant powder is frequently used to remove rocks, tree stumps, and other obstacles to cultivation or construction, it is not an easy thing to get a satisfactory photograph showing the actual explosion of a blast. The photographer must be near enough to the center of activity to secure a detailed picture; he must watch the progress of the explosion, and expose the plate at just the right instant; and, besides all this, he must be able to save himself and his camera from the stones and debris flying through the air.

The photograph here reproduced was made in a little town named Stirling City, in California. The blast was designed to remove a stump in the roadway. The camera was set up in a partly-finished house about twenty-five yards from the stump. When the fuses were lighted, the photographer stood with one hand on the bulb and the other holding the tripod head. After exposing the plate in the camera, he retired behind the walls, dragging his photographic apparatus with him. A moment later the stones and dirt that had been thrown up into the air came rattling down upon the house, some even coming through the window from which the picture had been made. The resulting picture is certainly a successful one, being clear in detail and filling the plate satisfactorily.

NEW 25-KNOT BRITISH SCOUTS.

The spirited picture of the new British scout "Sentinel," herewith shown, represents one of a class of eight vessels which have been designed solely to do scouting work. They carry only sufficient armament to drive off or destroy an enemy's torpedo boats or destroyers. Should this vessel meet with a hostile cruiser, it would not attempt to fight, but would instantly turn and run; or cruise in the offing out of gunshot range, but keeping in touch with and observing the enemy. The prime requisites for a vessel of this class are that it shall be very fast, faster, indeed, than any protected or armored cruiser; that it shall be of sufficient size and power to maintain its speed in heavy weather; that, compatible with the preceding requirements, it must be as small and inconspicuous as possible; and that it must be thoroughly staunch and seaworthy. Its armament need only be heavy enough to

defeat any craft such as a destroyer or torpedo boat that is fast enough to overtake it; and it need carry but a moderate coal supply, its sphere of action being always within easy steaming of the main fighting fleet and its attendant colliers.



PHOTOGRAPH OF A BLAST OF DYNAMITE.

These vessels were laid down a few years ago in accordance with the modern policy of the British navy, which is to reduce the larger ships of the navy to three distinct types—the battleship, the armored cruiser, and the fast scout. The battleship will form the nucleus and the main fighting element of the fleet. Spread out fanwise beyond them will be the fast armored cruisers of 23 to 24 knots speed, and beyond these in a wider circle will stretch the scouts of 25 knots speed. Hitherto the extreme outpost duty or duties of reconnaissance have been performed by cruisers of large dimensions, 6,000 to 10,000 tons displacement or more. But the number of large vessels is limited by their great cost; and it was realized that by reducing the size, raising


the speed, and trebling the number of vessels, the work of reconnaissance would be carried out over a far wider area, and by units that were in closer touch with one another and with the main body of the fleet.

Both the United States and Great Britain are building vessels of this type, or rather the British have built, and we are about to build them. In our issue of February 11 we illustrated the scouts designed for our navy, and a comparison of the two designs will be found very interesting. It will be seen from the accompanying table of dimensions that the British ship is smaller, faster, carries much less coal, and is considerably less conspicuous than our vessels. This is probably accounted for by the fact that our scouts are intended to act, if need be, on isolated duty, which may involve steaming over long distances, where there would be no access either to a collier or the coal pile.

The "Sentinel" is a vessel 360 feet in length and 40 feet in beam, displacing 2,920 tons. She has a high forecastle, to enable her to meet heavy seas, but otherwise she lies low in the water; her smokestacks are unusually short, and she is very inconspicuous—a valuable feature in scouting. She is provided with a single signaling mast, and indeed, in respect of her appearance, is merely a magnified torpedo-boat destroyer, her displacement being about seven or eight times greater than one of these craft. The steam trials prescribed by the Admiralty were that the vessel should steam for ninety-six hours at cruising speed, and that the rate of coal consumption on the latter half of this run should determine the quantity of fuel that the vessel was to carry when running at full power on her trial trip. She was to have sufficient fuel on board to enable her to steam at cruising speed for 1,500 miles; and with

COMPARISON OF BRITISH AND AMERICAN SCOUTS.

	British.	American.
Length, feet.....	360	420
Beam, feet.....	40	46½
Displacement, tons....	2,920	3,750
Horse-power.....	17,500	16,000
Speed, knots.....	25.24	24
Normal coal supply, tons.....	150	500
Armament.....	Ten 3-inch, eight 3-pounders	Two 3-inch
Torpedoes.....	Two 18-inc.	Two 18-inc.
Freeboard, forward.....	24 feet	24 feet
Freeboard, aft.....	14 feet	14 feet



Length, 360 feet. Beam, 40 feet. Displacement on trial, 2,920 tons. Horse-power, 17,500. Speed, 25.24 knots. Normal Coal Supply, 150 tons. Battery, ten 3-inch guns, eight 3-pounders. Torpedo tubes, two 18-inch on deck. Armor, 1½-inch deck.

The eight vessels of this class are intended for the same duties as the new United States scouts, illustrated in our issue of February 11, with which they may be compared.

NEW 25¼-KNOT BRITISH SCOUT "SENTINEL," FASTEST CRUISER AFLOAT.

this allowance of coal, and a load equivalent to the prescribed weight of ammunition, guns, etc., the vessel was required to steam continuously for eight hours, at a speed of 25 knots an hour. In the cruising speed trials it was found that one ton of coal was sufficient to carry the ship for 11 sea miles. On the eight hours' full-power trial, the engines worked up to a collective indicated horse-power of 17,500, and the mean speed for the whole run of 202 knots was 25.24 knots per hour. Incidentally, it may be mentioned that the load thus propelled is more than five times the average weight of a freight train making about the same speed on the rails.

As a measure of the cost of high power, it may be mentioned that the records of the trial show that to increase the speed from 22½ knots to 25 knots involved doubling the power required for the former speed. And further, that the last knot, that is the advance from 24 to 25 knots, involved a quarter of the maximum power, or an addition of over 4,000 horse-power, which, by the way, proved sufficient to drive the vessel at 19 knots an hour.

As showing how largely the great increase in horse-power and speed of modern warships has contributed to their cost, it may be mentioned that during the course of the trials, the new scout steamed around one of the armored cruisers of sixteen years ago, which was being taken under tow to her moorings, where she is to lie as an obsolete ship until she is sold. This cruiser of sixteen years' standing cost only about 25 per cent more than the modern vessel, although she has a displacement tonnage three times as great as that of the "Sentinel." In the case of the cruiser, the proportion of power to tonnage is barely 1 horse-power to 1 ton; whereas the "Sentinel" has 5¾ horse-power per ton; and consequently, her cost per ton is very much greater than that of the older but larger ship.

MY SCIENTIFIC EDUCATION.

BY THE RT. HON. LORD KELVIN.

I am a child of the University of Glasgow. I lived in it sixty-seven years (1832 to 1899). But my veneration for the ancient Scottish University, then practically the University for Ulster, began earlier than that happy part of my life. My father, born in County Down, was for four years (1810 to 1814) a student of the University of Glasgow, and in his Irish home, as first professor of mathematics in the newly-founded Royal Belfast Academical Institution, his children were taught to venerate the University of Glasgow. One of my earliest memories of those old Belfast days is of 1829, when the joyful intelligence came that the Senate of the University of Glasgow had conferred the honorary degree of Doctor of Laws on my father. Two years later came the announcement that the Faculty of Glasgow College had elected him to the professorship of mathematics. My father's experiences as a Glasgow student are naturally of supreme interest to myself. There were no steamers, nor railways, nor motor cars in those days. Can young persons of the present time imagine life to be possible under such conditions? My father and his comrade students, chiefly aspirants for the ministry of the Presbyterian Synod of Ulster and for the medical profession in the North of Ireland, had to cross the channel twice a year in whatever sailing craft they could find to take them.

At the beginning of his fourth and last university session, 1813-14, my father and a party of fellow students, after landing at Greenock, walked thence to Glasgow. On their way they saw a prodigy—a black chimney moving rapidly beyond a field on the left-hand side of their road. They jumped the fence, ran across the field and saw to their astonishment Henry Bell's "Comet" (then not a year old) traveling on the river Clyde between Glasgow and Greenock. Their successors five years later found in David Napier's steamer "Rob Roy" (which in 1818 commenced plying regularly between Belfast and Glasgow) an easier, if a less picturesque and adventurous way between the college of Glasgow and their homes in Ireland. Those students who had experience of cross-channel passages before and after the advent of the "Rob Roy" may well have been grateful to their college, not only for what it did for themselves but for what sixty years before it did for steam navigation in giving to James Watt a scientific home and congenial friends, and a workshop in the old University territory adjoining to the High Street of Glasgow. In the course of his four student years my father attended the classes of humanity, moral philosophy, mathematics, natural philosophy, anatomy, divinity. Though his passion was for science, and especially mathematics and natural philosophy, he attended during his first three sessions and won prizes in the Latin class, then happily, as now, called humanity. It is scarcely possible to over-estimate the life-long good gift presented to a scientific student one hundred years ago, as now, by universities in giving something of the *literæ humaniores* to all who can and will take it.

In 1834, two years after my father was promoted

from Belfast to the Glasgow Professorship of Mathematics, I became a matriculated member of the University of Glasgow. The little tinkling bell in the top of the college tower, calling college servants and workmen to work at six in the morning; the majestic tolling of the great bell wakening at seven o'clock professors (and students, too, I believe, in the olden times, when students lived in college); then, again, the lively little tinkling bell calling the professors and students of moral philosophy and senior Greek and junior Latin at half-past seven to work in their classrooms. Woe to the student of Latin who reached the door ten seconds after the quick little bell's last stroke. He was shut out by the door-keeper, unfailingly ruthless, by inexorable order, and had to wend his way through the darkness to his lodging, sorrowfully losing the happy hour's reading of Virgil or Horace or Livy with his comrades, under their bright young professor, William Ramsay, and knowing that he had got an indelible black mark against his name. Rarely did even a single student of a large class experience this disaster. It was a sharp, healthy, beneficial discipline, rigorously maintained by one of the kindest and most considerate of all the professors who have ever guided students in the Scottish universities.

As to Latin, I followed my father's example and attended divisions of the class during three sessions. To this day I look back to William Ramsay's lectures on Roman antiquities and readings of Juvenal and Plautus as more interesting than many a good stage play that I have seen in the theater. Happy it is for myself that his name and a kindred spirit are with us still in my old friend and colleague our senior professor, George Ramsay. Greek, under Sir Daniel Sandford and Lushington, logic under Robert Buchanan, moral philosophy under William Fleming, natural philosophy and astronomy under John Pringle Nichol, chemistry under Thomas Thomson (a very advanced teacher and investigator), natural history (zoology and geology) under William Cooper, were, as I can testify by my own experience, all made interesting and valuable to the students of Glasgow University in the thirties and forties of the nineteenth century. Sandford, in teaching his junior class the Greek alphabet and a few characteristic Greek words, and the Scottish pronunciation of Greek, gave ideas and something touching on philology to very young students, which remains on their minds after the heavier grammar and syntax which followed have vanished from their knowledge. Logic was delightfully unlike the Collegium Logicum described by Goethe to the young German student through the lips of Mephistopheles. Even the dry bones of predicate and syllogism were made by Prof. Buchanan very lively for six weeks among the students of logic and rhetoric in Glasgow College sixty-seven years ago; and the delicious scholastic gibberish of *Barbara celarent* remains with them an amusing recollection. A happy and instructive illustration of the Inductive Logic was taken from Well's Theory of Dew, then twenty years old. My predecessor in the Natural Philosophy Chair, Dr. Meikleham, taught his students reverence for the great French mathematicians, Legendre, Lagrange, Laplace. His immediate successor in the teaching of the Natural Philosophy class, Dr. Nichol, added Fresnel and Fourier to this list of scientific nobles; and by his own inspiring enthusiasm for the great French school of mathematical physics, continually manifested in his experimental and theoretical teaching of the wave theory of light and of practical astronomy, he largely promoted scientific study and thorough appreciation of science in the University of Glasgow. As far back as 1818 to 1830 Thomas Thomson, the first professor of chemistry in the University of Glasgow, began the systematic teaching of practical chemistry to students, and by aid of the Faculty of Glasgow College, which gave the site and the money for the building, realized a well equipped laboratory, which preceded, I believe, by some years Liebig's famous laboratory of Giessen, and was the first of all the laboratories in the world for chemical research and the practical instruction of University students in chemistry.

In the province of the humanities the working power of the University for instruction and research has been largely augmented during the last fifty years by the foundation of new professorships, conveying, English language and literature, Biblical criticism, clinical surgery, clinical medicine, history (in my opinion the most important of all in the literary department), pathology, political economy. In mathematics and in the science of dead matter, professorships of naval architecture and geology; lectureships of electricity, of physics, and of physical chemistry; and demonstratorships and official assistantships in all departments have most usefully extended the range of study, and largely strengthened the working corps for research and instruction.

A plan is under consideration by Salt Lake City authorities to provide automobile street sweepers.

A TACHOMETRIC WATCH FOR BICYCLES AND OTHER VEHICLES.

(Continued from page 160.)

The hand, then, does not budge relatively to the vehicle, and remains in an invariable position with respect to the handle bar of the bicycle, for instance, if the instrument is mounted on one of these. Since the velocity thus communicated to the case by the wheel does not vary, the rider is sure that he is moving at a constant velocity as long as the hand does not appear to have moved. If, after the hand has appeared to have moved, it is turned back to its original position, the rider is sure to have run on an average at a constant speed. This speed corresponds to the ratio of the gearing existing between the case and the wheel. The tachometric watch, therefore, supposing that it is proposed to travel at so many miles an hour, permits of gaining speed in a descent or of losing it in slowing up or stopping. If, afterward, the rider, by increasing or decreasing the speed, succeeds in bringing the hand back to its initial position with respect to the handlebar, he will be sure of having run at the mean speed corresponding to the ratio of the transmission. The hand considered is the hour one, or, generally, that of the seconds placed in the center of the dial. In this case, it is possible to read the deviations in speed to within a minute. It must be recalled, however, that the hand has lost or gained several revolutions, in order to bring it behind or before the exact number of revolutions by which it has varied. The mean speed that is obtained by keeping the hand apparently stationary depends upon the reducing ratio of the transmission. This ratio may be changed at will, without dismounting from the machine, in such a way as to cause a variation in the speed that it is desired to preserve on a gradient or on a level. With this object in view, the manufacturers, MM. Chateau et Fils, of Paris, are constructing two kinds of tachometric watches, one of them operating with a movable pinion and the other having a rubber belt for actuating the case.

The first type gives no error of transmission, since everything is done by gearing. To the axle of the front wheel of the bicycle is fixed a star-wheel, and a rod actuated by this controls an endless screw that drives a horizontal shaft having keyed to it a sharp-toothed pinion which can be slid along it. This pinion gears with a disk at different positions through apertures arranged in circles. Each circle is provided with a different number of apertures, and equal to the number of millimeters of its diameter. It is necessary, according to the circle with which the toothed wheel gears, to run with greater or less speed in order to keep the hand inoperative. Figures from 1 to 9 are marked upon a division, and the toothed wheel is arrested opposite figures corresponding to the speed in kilometers per hour, indicated opposite each figure upon a reckoning device. There can be no error except by reason of the imperfect regulation of the watch. If the latter varies 5 minutes a day, the error committed in the estimation of the speed will be 1-144, which error is therefore practically of no consequence.

The second type is more simple, but gives rise to errors due to slippage, amounting to about 0.02 at the most. The star-wheel is the same as in the other type. The watch is inclosed in a revolving case mounted on a collar which is screwed to the handlebar and is operatively connected with a drum actuated by a rubber belt passing over different channels, each of which corresponds to a determinate speed. The principle of the apparatus is the same as that of the preceding type.

Both types may be provided with a differential counter formed of two disks of 99 and 100 teeth that gear with the endless screw that actuates the case. The disks revolve in unison, and one of them is graduated from 0 to 100 and the other from 0 to 10,000. These numbers represent every twelve meters made by the wheel. A stationary index indicates up to 100 dekameters, and a movable one up to 10,000. The accuracy is within about 10 centimeters.

A 100-Mile Automobile Road Race in Cuba.

On the 12th instant the automobile racing invasion of Cuba was completed by the running of a 160-kilometer (99.36-mile) road race. The race was run over a fine stretch of road from Havana to San Cristobal and return, there being one neutralized stop at the turning point. On account of a collision a few days before, in which he was injured slightly and his mechanic Hawley rather seriously, E. R. Thomas was unable to compete with his 90-horse-power Mercedes. Tracy drove Major C. J. S. Miller's (formerly Mr. W. Gould Brokaw's) 30-horse-power Renault racer, and Fletcher drove an 80-horse-power De Dietrich. The race was won by Mr. E. K. Connill's 60-horse-power Mercedes, driven by Ernesto Carricaburn, a young Cuban. His time was 1 hour, 50 minutes, 53.35 seconds. The Renault was second in 1:52:26. This machine had trouble with the battery shaking loose, which delayed it somewhat. Otherwise, it would have undoubtedly won.

AN EASILY-CONSTRUCTED ROTATING ANODE EQUIPMENT FOR RAPID ELECTRO-ANALYSIS.

BY N. MONROE HOPKINS, PH. D.

Having employed for some time past, with much success, a rotating anode for rapid electro-deposition, the construction of the equipment is deemed of sufficient interest to warrant its illustration. With such a piece of apparatus metals can be completely precipitated in a few minutes, whereas with a stationary anode it was necessary to employ such feeble electric currents that several hours were required. It may be stated that the effect of the rotating anode is to maintain a homogeneous electrolyte, by preventing concentration changes due to differential ion velocity. The construction of this outfit is exceedingly simple, as will be seen from the drawing, consisting of a vertical board firmly bolted to a heavy base by angle irons, and supporting an electric motor mounted with its shaft in a vertical position. A few words about this motor are necessary, for it will be the tendency of those making this apparatus to buy a very small battery motor, as in reality it has practically no work to do in rotating the platinum wire in the solution. A very small motor is very unsatisfactory, as it cannot be operated in connection with a lighting circuit, even by using a lamp bank. A large motor is easily controlled in speed and adjustment, and runs smoothly and without attention. Directly under the commutator, upon which copper or preferably carbon brushes feed, is a large metal disk to prevent any minute particles from falling into the solution. The platinum dish should rest upon a sheet of platinum supported on an adjustable stand, in order that the dish may be quickly lowered to remove the anode. At the extreme right in the illustration we have a panel board with the necessary electrical instruments for maintaining the proper electrical conditions for this character of work. In all reports upon electro-deposition it is necessary to state the current flow, the current density, the electrode tension, and temperature in addition to the character of the solution, etc. This illustration is taken from the author's series of articles upon "Experimental Electrochemistry," appearing bi-weekly in the SCIENTIFIC AMERICAN SUPPLEMENT, where a more detailed account of electro-analysis is given, and where those interested in this subject may turn for certain recent laboratory data.


A HUGE ELECTRO-MAGNET FOR OPTICAL AND SURGICAL WORK.

The greatly increased speed of mechanical tools which has been made possible by the introduction of the "new steel," and the resulting increase in the velocity of particles of steel which by chance may strike the eye, have caused oculists to look for electro-magnets of far greater attractive force than those heretofore constructed for this line of work. To meet this demand, at the request of Dr. F. M. Wilson, the oculist on the medical staff of the Bridgeport, Conn., General Hospital, the author of this article designed and assembled the electro-magnet illustrated herewith, which, for the use of the profession, is probably the largest magnet thus far constructed.

On account of its great weight, it was not deemed advisable to make the instrument movable, as the necessary frame would occupy more space than could be given in a physician's office. The vertical position has not been found inconvenient, however, in actual use. The iron core of the magnet is four feet long and six inches in diameter. It is bolted to a base of oak, and its upper part is tapered so as to enable the oculist

to conveniently observe the patient's eye with an ophthalmoscope. The point of the tapered portion of the core unscrews, so that it may be treated antiseptically, and on this point is a brass piece carrying a small brass ring. The patient rests his face on this ring, which is of such a height that the eyelashes just touch the extremity of the conical point. The magnet requires 30 amperes at 110 volts to completely saturate the core, which is wound in two halves with 235 pounds of No. 7 B. and S. gage copper wire wrapped with a special insulation of cartridge paper in place of

the usual cotton thread. The powerful lines of force of the magnet are illustrated in a measure by dropping iron filings on a piece of cardboard placed on its top. The filings build up in a pile, being held in place by the magnetic attraction as shown in one illustration. Another picture shows how stray pieces of metal can be held against a person's face when the back of his head is placed against the magnet. The third photograph illustrates the method of procedure followed in drawing a piece of steel out of one's eye. The magnet is particularly useful in diagnosing cases in which a



AN EASILY-CONSTRUCTED ROTATING ANODE FOR RAPID ELECTRO-ANALYSIS.


piece of metal is thought to have become lodged in the eye, but in which the oculist is not sure of it. By placing the eye of the patient above the magnet, as shown, and sending a small current through its coils, the presence of a piece of steel will be immediately felt by the patient, because of the magnet's attraction for the steel. The magnet may be used in surgery in the same way. If a piece of steel or iron has been driven into any part of the body, its location may be determined at once by simply approaching the magnetic field. Further, if the wound is recent, the piece of metal immediately returns by the same course it entered without any surgical interference.

In one instance a piece of a hammer head had been driven into the muscles of the upper arm, and in another case a piece of a cold chisel into the forearm. In these two cases the surgeons advised no operations, trusting to the pieces working out of themselves; but the wounds became infected and the magnet was tried. The success of the method was complete, the pieces of metal appearing immediately on the polar piece. Possibly the operations on these were the first ever performed wherein a powerful electro-magnet had removed metallic pieces, if we except cases of the eye.

Since then, at the Bridgeport hospital, pieces of steel have been removed from the hand. In one case a chip of steel had been embedded in the palm of a man's hand for a year and a half, and in another a piece had been in the back of the hand for seven years.



Position of Patient When Removing Steel from the Eye.



Showing the Lines of Magnetic Force by Means of Iron Filings.



Pieces of Iron and Steel Held in Place by Magnetic Attraction.

A HUGE ELECTRO-MAGNET FOR OPTICAL AND SURGICAL WORK.

Both were encysted, but they immediately appeared on the magnet when the skin was slightly opened, a protuberance caused by the magnetic attraction indicating the locality.

A broken sewing needle that caused much pain and produced considerable swelling was instantly removed from the palm of a woman's hand. These cases, all of which were successful, would make it seem that powerful electro-magnets could be of great use in military hospitals for the removal of pieces of shells and steel bullets. As in the above-mentioned cases, which

were of recent occurrence, the particles made their exit through the same trauma by which they entered, there would no doubt be a similar result in gunshot wounds, surgical interference with its numerous dangers thus being avoided.

Some further particulars regarding this magnet and the calculations involved in designing and building the same will be found in the current SUPPLEMENT.

Fraud in Furs.

As a people we are very fond of fraud. We don't much care for law, and we love to be fooled. In no line of commerce are we more regularly fooled and defrauded than in the retail fur trade. The ermine which my lady buys for the collar of her opera coat cost her some dollars a skin. She may pay \$1 for the black tip of the tail of a single ermine skin. The trapper who caught the weasel from which came the ermine got, perhaps, ten cents for the skin; perhaps five; perhaps nothing. That is not so bad, and no one could object to a commercial transaction of that kind. A great many persons know that ermine is weasel. How many know that muskrat pulled and dyed is often sold as seal; that nutria similarly treated is sold as seal or beaver; that rabbit so treated is sold as seal or electric seal; that pulled and dyed otter is regularly sold as seal; that marmot dyed is sold as mink and sable; that fitch dyed is sold as sable, and rabbit also sold as sable; that hare and muskrat are sold as mink or sable, and white rabbit as ermine or chinchilla or fox; that goat is dyed and sold as bear; that many kinds of lamb are sold as Persian; that skunk is called Alaska sable; that American sable is sold as Russian crown sable; that monkey and lynx and dog and fox and polecat and muskrat and cat, and all sorts of different furs are sold under all sorts of high-sounding names; that white hairs are regularly inserted in fox skins and sometimes in sable skins? Surely not all of our readers were advised as to these details. There is a vigilance committee appointed by the London Chamber of Commerce whose duty is to spread information against these trade frauds. We presume we need nothing of that sort in America, for here we don't mind being fooled.—Field and Stream.

Another Patent Granted to Cornelius Vanderbilt.

Letters patent have recently been granted to Cornelius Vanderbilt for an improved locomotive tender. The object of the invention is to provide a simple and economical form of water-tank with a low water-intake and large capacity, to shorten the length of the tank without increasing its height, and to improve the construction of the fuel-hood.

The water-tank is elliptical in cross-section and has its major axis in a horizontal plane. This shape was chosen because such a tank has a larger capacity than a circular one of equal height, and because its center of gravity is lower than that of a circular tank of equal capacity. To prevent the water from rushing from one end to the other on starting and stopping, a series of baffle-plates is provided extending toward the center from the top and bottom of the tank. The lower plates are provided with suitable openings for the passage of the water. The tank is interiorly braced by angle-iron stiffening members riveted to the shell and extending entirely around it. The baffle-plates are secured to these braces.

The rear wall of the coal-hood is in effect a continuation of the end of the tank. The hood is provided with side-walls, a distance apart equal to the major axis of the cross-section of the tank. The rear end has sliding doors with handles. In front of it is a platform on which the fireman may stand.

The underframing of this car consists primarily of two longitudinal draft-sills which are connected directly to the shell of the water-tank, and which have mounted between them ordinary draft-rigging.

In the earlier forms of the Laval steam turbines, a 5-horse-power motor, with a diameter of 12 centimeters, made about 30,000 revolutions per minute.

ROCKY MOUNTAIN AVALANCHES.

BY DAY ALLEN WILLEY.

While avalanches or snow-slides frequently occur in the Rocky Mountain region, and many of them are of great magnitude, what is known as the San Juan district in southwestern Colorado is especially notable for these movements, owing to the formation of the ranges. Several of the peaks are over 13,000 feet in height, and the conditions are especially favorable for the motion of the snow, as the mountain sides are deeply cut with gulches, which form numerous routes. Consequently, not only in winter, but during the spring, miners and others working on the slopes of the mountains are obliged to be continually on the lookout, for frequently without warning an avalanche will descend with such



View of One of the Buildings Partly Wrecked.


force as to carry with it large forest trees and boulders, attaining such a velocity that it destroys everything in its path. Some of the avalanches have carried a bank of snow over 100 feet in depth into the valleys which they penetrate, the snow bed covering several acres.

Despite the caution exercised by the people on the mountain side, many fatalities have occurred, especially in the Telluride mining district, which is located in the San Juan region. The worst disaster thus far recorded occurred when a settlement in the vicinity of the Liberty Bell mine was struck. All the buildings in the path of the avalanche were destroyed. The wing of one of the mine buildings was torn away, and two engineers were buried in the snow. A party


(Continued on page 166.)



Mining Plant in the Outskirts of Telluride, Colo., Where One of the Most Destructive Slides Occurred.



The Avalanche That Wrecked the Mining Shaft. At Several Points the Snow Was Over 100 Feet Deep.



How the Forest Was Denuded by the Slide.



Ruin Caused by an Avalanche at Amer, Colorado.



Scene in the Valley After the Slide.

ANTIQUE WATCHES OF THE FAMOUS MARFELS COLLECTION.

BY CHARLES A. BRASSLER.

Perhaps the most wonderful collection of antique watches is the property of Carl Marfels, of Berlin. It includes only handsome specimens of great artistic value which have been culled from thousands of antique pieces.

Thanks to his great perseverance, Mr. Marfels succeeded in gathering a collection unique of its kind, consisting of superb specimens of the chronometric art from its inception to the eighteenth century. True, these watches are not time-pieces of great precision. Everybody knows that precision in watches dates only from the nineteenth century. The handsome works, however, present all the perfection that could be expected of their makers, and they are in every way worthy of the wonderful and artistically-worked cases in which they are inclosed.

While great progress has been made latterly in endowing watches with remarkable accuracy, it may truly be said that the artistic skill reached in the sixteenth, seventeenth, and eighteenth centuries in the decoration of the cases, dials, and cocks cannot be excelled. Thus we meet engraved watch cases and dials from the eighteenth century which fill the art lover with boundless admiration. Enamel paintings have been preserved from the seventeenth century which could not be produced at the present time in such perfection. Think of the goldsmithing work in the watches of the seventeenth and eighteenth centuries, the precious stone embellishments, the chasing, *repoussé* work, the application of four-colored gold, the vernis Martin, filigree work.

The accompanying illustrations cannot even faintly reproduce the beauty of the originals, as they lack the gorgeous colors of the enamel and the sparkle of the precious stones which can only be indicated in black and white, nor do they give an adequate idea of the fineness of the engraved and pierced work. Still, they may serve to show the reader the high degree of perfection attained by the decorative arts in former centuries.

It is to be hoped that this beautiful collection, if it should ever be on the market, through death or otherwise, will be acquired by one of our art lovers or museums, and thus, like so many other charming works of art, ultimately come to America, where it is certain to be admired and appreciated as much as anywhere in the world.

As is well known, Peter Henlein, of Nuremberg (about 1500), is now generally credited with the invention of the portable watch, and a movement is on foot to erect a monument to the memory of this ingenious locksmith in his native city.

The earliest watches were naturally rather crude; this is shown by the few specimens still in existence

(see Figs. 1 and 2). They were circular in shape (not oval or egg-shaped), and entirely made of iron. In place of the round balance we find a straight one called "foliot." Like almost all watches up to the year 1790, they were provided with the verge escapement. The hair spring is, of course, absent; it was not invented till 150 years later. In order to obtain a tolerably uniform rate an upright hog's stile (the dot at which the arrow *a* in Fig. 2 points indicates where the bristle is situated) was used against which the foliot strikes. The uneven traction of the spring they endeavored to prevent by means of a brake. Great accuracy was not aimed at, which is shown by the fact that the oldest watches with very few exceptions up to about the year 1700, indicated only the hours, the minute hand being entirely absent.

While the first watches were rather crude, we see, only 20 or 30 years after their invention, works that

Toward the year 1800 we meet for the first time the seconds hand in verge as well as cylinder watches. The cylinder escapement is known to be quite old; for it was originated as far back as 1710, but was not generally adopted until about 1840. The lever escapement, the one used in the majority of our American watches of the present time, was invented about 1765 by Thomas Mudge. No lesser artist than Pierre le Roy is the originator of the duplex escapement, which was contrived by him already in 1748, but like the cylinder escapement was not introduced until a whole century had elapsed.

A few remarks regarding the traits by which the age of watches may be determined will doubtless prove of interest. It is now definitely known that the egg-shaped watch is not the oldest form, as was formerly supposed. They are not met with till the middle of the sixteenth century; most of them date back

to the period around 1600. Enamel painting in colors was invented in 1632, hence there were no watches decorated with enamel till that time. As stated before, the balance spring was invented as far back as 1658, but only rarely employed, and did not become more general until about 1690. Watches with striking mechanism were already carried in the sixteenth century, but repeaters were not invented before 1691, and only became frequent about 1720; while alarm watches were used as far back as in 1600. The minute hand was introduced only with the use of the balance spring, hence it is not met with in watches of older construction than the close of the seventeenth century. The cylinder escapement, though invented in 1710, is only found in isolated cases in the eighteenth century; almost all pocket watches till the beginning of the nineteenth century had verge escapements. Watches with chased cases do not occur before the beginning of the eighteenth century; most of them date from the period about 1750. Decoration in four-colored gold (*quatre couleurs*) is not



1.—Early cylindrical watch; 2.—Foliot and hog's bristle of cylindrical watch; 3.—A richly-worked bronze watch; 4.—Egg watch; 4a.—Side view of egg watch; 5.—Silver cross watch, Amsterdam, 1650; 6.—Egg watch, Amsterdam, 1650; 7.—Gold-enamelled egg watch, 1600; 8.—Engraved egg watch, indicating week, date and phase of moon; 9.—Smallest of old watches (9 mm. or 0.354 inch in diameter); 10 and 10a.—Engraved watch made by Gamod, 1640; 11.—Watch with religious scenes, 1700; 12.—Watch set with pearls and inclosing a music box; 13.—Watch made by Albery, London, 1800; 14.—Gold box containing a bonbonnière and a wren that chirps; 15.—Tulip watch of gold, inlaid with pearls, 1800; 16.—Mandolin watch with filigree work; 17.—Rock crystal watch with engraved dial.

HISTORIC WATCHES IN THE MARFELS COLLECTION.

may almost be termed technically perfect. The iron plates and wheels had given place to finely gilt brass ones. The pinions are of steel and polished, the cocks artistically engraved, and the pillars neatly turned.

Greater precision was obtained when about the year 1660 the hair spring was invented by Dr. Hooke (and also, but entirely independent of the latter, by Huyghens). This opened the way for the introduction of the minute hand, which we meet quite generally around the year 1700. Some of the oldest watches were already furnished with a striking mechanism. About the year 1600 there were watches with alarm made, and in 1691 Barlowe, an Englishman, introduced the repeating watch.

The invention of the fusee is also quite old. The Marfels collection contains a table clock with spring and fusee dating from 1509.

found before the year 1770. The gong is first used about 1800. Movable figures on the dials, figures that beat upon bells, millwheels, etc., do not occur before 1790, musical watches not till about 1800, nor were there any watches set with pearls before that period. Pocket time-pieces having the form of mandolins, harps, enameled shells, tulips, flasks, balloons, finger rings, and similar objects generally fall in the period from 1800 to 1820. Pierced cases, usually decorated with foliage and animal figures, date mostly from the time 1670 to 1720. Rock-crystal cases usually date from 1550 to 1650. Watches with stone cases, agate, jasper, as well as those decorated with precious stones, generally date from the eighteenth century. The very flat cylinder watches, generally with a pin for winding, were made around 1840. The earliest watches were cylindrical in shape. From the year 1550 to 1680 they were made

flatter. With the adoption of the balance spring about 1690, the watches became very thick, almost spherical, till they were made flatter again around 1770, to reach toward the year 1800 the thickness of the present watch.

A few words respecting the value of old watches may not be amiss. Valuable are all watches whose cases and dials are artistically decorated, the essential and prime condition, however, being that the cases are eminently handsome and well preserved. The state of preservation of the works is of no importance whatever, but that of the case and dial is so much more vital. All watches of the very oldest types (with iron works) are also valuable, as well as all egg watches, watches with finely pierced or handsomely chased cases that show no wear, gold enamel watches, which are enameled inside and outside, and all watches in general that are handsomely decorated in any respect.

The following are, on the other hand, valueless or almost so: Chased watches whose figures are worn off; watches with painted tombac cases (copper enamels); watches with cases decorated with gold in four colors unless very beautifully executed and well preserved; watches with enamel-painted dials (enameled on copper); enameled watches which are much damaged; all watches which are devoid of any artistic decoration, hence silver and gold watches with plain cases and unadorned dials, no matter of what description the works may be.

In Fig. 1 is shown a cylindrical watch from the earliest time of watchmaking. The work is entirely of iron, with the so-called foliot (Fig. 2) and hog's bristle (see arrow *a*, which shows the dot marking the spot where bristle is) in place of a balance. The case is of bronze in charming chased work, a masterpiece of the sixteenth century.

A beautiful specimen handed down from the same century is the bronze case in wonderful pierced work depicted in Fig. 3. There are on its periphery four openwork rows of inscriptions and devices, such as: "Hingeit die Zeit, herkompt der Tod, o Mensch thue Buss und fürchte Gott," etc., as well as one in Greek.

Highly interesting is the little egg watch shown in Fig. 4. It has a handsomely enameled dial, which on the back shows in raised enameled work St. George with the dragon. The sides of the case bear the inscription of the Order of the Garter: "Honi soit qui mal y pense." (See Fig. 4a.) At the Spitzer auction this gem of the goldsmith's art brought 21,500 francs (No. 2,711 in the catalogue of the auction). Signed N. Vallin; time about 1600.

Fig. 5 shows us a silver cross watch with fine openwork case, depicting hunting scenes, remarkable for its rare work. Signed Carl Bauer, Amsterdam; time about 1650.

An egg watch in a finely-engraved silver case, partly gilt, is represented in Fig. 6. Signed Jacop Ducimin, Amsterdam. From the Spitzer collection. Time about 1650.

In Fig. 7 we see a gold-enameled egg watch. It dates from about 1600.

A veritable *chef d'œuvre* of the engraver's art, an egg watch in a silver-gilt case, indicating the day of the week, date, phase of the moon, zodiac, and age of the moon, is depicted in Fig. 8. The plates are superbly engraved. It belongs to the time around 1850.

The smallest watch of former centuries appears in Fig. 9; its diameter is nine millimeters. It has a gold enameled case and dial. This unique specimen is a product of the middle of the seventeenth century.

Notable among the gold-enameled watches in this collection is the one shown in Fig. 10, from the period of Louis XIII., with representations from the story of Anthony and Cleopatra on the inside and the outside of the case (Fig. 10a). This watch was made by C. Gamod at Paris about 1640. Another gold-enameled watch, likewise an excellent piece, shows scenes of the Madonna, etc. (Fig. 11); from the period around 1700.

Still another large gold-enameled watch is set with pearls and contains a music box playing on bells (Fig. 12). The back is decorated with lions and swans belching forth water (in operation); the inner rim charmingly engraved and pierced. A unique work of the first class from 1790.

Fig. 13 represents a gold watch, set with pearls, in translucent enamel. Signed Albery, London; time 1800.

Very odd is a gold box, the lower part of which serves as a *bonbonnière*, while the upper part, executed in the form of a watch, contains a willow-wren chirping a melody, with the corresponding motion of the beak, flapping its wings, and moving in a lively manner (Fig. 14). The whole is finely enameled and dates from about 1790.

Other odd shapes are shown in Figs. 15 and 16. The former is a tulip of gold inlaid with pearls and enameled (about 1800), while the latter is a gold watch in the form of a mandolin, in filigree work, set with pearls, from about the same period.

As want of space prevents me from illustrating all of the interesting ninety-odd pieces of the collection,

I will close by presenting in Fig. 17 a rock-crystal watch with handsomely engraved dial. This watch was made around 1650, and once formed part of the Spitzer collection.

ROCKY MOUNTAIN AVALANCHES. (Continued from page 164.)

of miners started to rescue the engineers when another avalanche descended, burying nearly twenty of the rescuers. In all no less than six masses of snow came down the slope during that day, and the bodies of the victims were not recovered until several months afterward. The snow was so deep that portions of the avalanche remained in the valley until late in the summer. A few days later the San Juan mine situated near the Liberty Bell was literally overwhelmed by an avalanche. A number of incidents have occurred in the San Juan district and other parts of Colorado which strikingly indicate the force of the snow movement. In one instance a gang of railroad men on the Colorado & Northwestern line were removing the snow from the track at a point near Long's Peak. Here the railway was built at an elevation of about 10,000 feet, but the mountain extends over a thousand feet above it. A rotary snow plow pushed by two locomotives, each weighing over fifty tons, was employed to clear the track, when a slide came down, of such dimensions that one of the locomotives was lifted from the rails, torn away from the other engine and carried nearly 500 feet down the slope with two of the men, who were killed.

Usually the mass of snow descends early in the spring, when the rays of the sun have weakened it sufficiently to create a movement. As soon as spring approaches, the townspeople carefully note the appearance of the dangerous snow fields and prepare for their descent, which is usually in one direction. When the Denver & Rio Grande Railroad was constructed to Telluride, the engineers learned of the yearly snow slide and surveyed a route which they thought would prevent it from endangering the track. The first spring after the road was completed, however, for some unknown reason the avalanche took a different course, striking the railroad with such force that no less than twenty-five loaded freight cars were thrown down the mountainside and destroyed. Fortunately the avalanches in Telluride have been made the subject of a special study by one of its residents, Dr. J. Q. Allen, who has obtained much valuable data as to their cause and effect. Dr. Allen had an opportunity to observe the first avalanches that damaged the Liberty Bell mine. His statement, which follows, is of special interest:

"The first slide at the Liberty Bell mine ran at least one mile. The snow was left 25 feet deep in the gulch, and probably much more than that in places, possibly a maximum depth of 40 feet. There was no mass of ice in the slide, only snow, solidly packed by the impact of the moving mass. The vertical distance which this slide descended was fully 3,000 feet. The slides all started above timber line, at an altitude of from 12,000 to 13,000 feet. The first 1,000 feet of the course of the slide referred to was at an angle of about 4 deg., the next 500 feet, 20 deg., and the balance of the way about 15 deg. from horizontal. Of course, the upper part of the range is much steeper than this, in places almost perpendicular; but the snow does not accumulate to any extent on such a steep surface, merely striking against the wall of rock and falling down to where it can stick to the surface until it accumulates to great depth. The current of air produced by an avalanche is often something terrific. The swiftly-moving mass of snow creates an air pressure in front and a partial vacuum behind, producing currents strong enough to destroy buildings untouched by the snow. The difference in air pressure within and outside of a building is sometimes sufficient to actually blow the structure to pieces. Of course, avalanches usually run in well-beaten tracks; but occasionally the wind will so drift the snow as to throw the slide out of the regular course. This explains why we often see a slide cutting down through timber, which is evidence in itself that no slide has run there for many years before. The causes which operate to start the slide are various. When a heavy fall of snow has taken place early in the winter, as soon as it is heavy enough it will move regardless of the time of day or of any other influence. Slides that occur in the month of April are usually caused by the heat from the sun. Where a large field has accumulated high up on the side of a mountain, and has been frozen to the earth, it will remain until the heat of the sun loosens it from the bottom. In our locality these slides usually start about four o'clock in the afternoon. In loose, freshly-fallen snow, very little force is needed to start a big slide. The firing of a gun or a sudden gust of wind may be sufficient. If a small bunch of snow, no larger than an orange, drops from a little cliff and starts rolling down the side of the mountain, it may enlarge rapidly enough to start an immense avalanche."

Dr. Allen has made measurements of forest trees which have been cut down at the base by the force of the moving snow and found that many of them ranged

from 15 to 18 inches in diameter; yet, as the photographs show, they were reduced to a mass of debris, and in many instances the trunks were stripped of their branches. Dr. Allen has personally had several thrilling experiences with snow slides in Colorado and was one of those who escaped in the Liberty Bell disaster. His account of his experience contains some valuable data and is here given:

"My first experience with a slide was at Creede, Col. I, with three other men, was on the side of a mountain looking at some mining property. We were above timber line and about half way from the bottom of the gulch to the top of the mountain. I did not think at the time of danger, as the snow where we were was only about 18 inches deep. The field suddenly cracked and the snow below us moved down a foot or two. This took away the support of an immense mass of snow above us, where it had blown over the top of the ridge to a depth of 15 or 20 feet. It broke at the crest of the ridge, and all of the snow on our side of the mountain came rushing down upon us. The mountain curved around us in a circular manner and the width of the slide was more than 1,000 feet, we being about in the center. I glanced up, on hearing the snow break, and, acting upon my first impulse, turned my back to the avalanche. It struck me first on the legs, and I sprang into the air as high as I could. The mass passed under me, and by the terrific rush of the snow I was kept on the top all the way down into the gulch, about 500 feet. I was the only one free, and proceeded to dig the others out. As the snow frequently packs after running, almost to the consistency of ice, this was no easy matter. The man next to me was buried in a perpendicular position, with only his hair visible. I had to free his body down to the ankles before I could pull him out. The last man reached was dead when extricated. The rest of us escaped with slight bruises. It was the next July before articles we lost were found. When the Liberty Bell disaster occurred, I was conducting a hospital for the mining companies. Receiving news of the first slide, I went to the mine, finding several men who were severely injured. After attending them, I sent them down to the hospital. About eleven o'clock the second slide came down in the track of the first slide, starting a little to one side, and burying several of those in the gulch searching for the dead and injured of the first slide. We then decided to leave the locality, taking the injured with us. After passing over the next ridge and on coming down into the gulch beyond, the third slide came down. This slide ran almost a mile. I was the last man in the procession. A heavy snow storm prevailed, so that we could see only a few feet, but as I knew we were about to cross the old track of a slide I kept listening. Presently I heard the breaking of timbers far up the side of the mountain. This could be distinctly heard above the roar of the storm. Turning my horse, I ran him up the trail just in time to escape the main body of the slide. I was caught on its edge, however, carried off the trail with my horse and tossed, as by a wave, on the side of the mountain, where the slide made a turn. Four of us were struck by this slide, and all were killed but myself. In all twenty-three men were killed at this place by slides that day."

Method of Making Violins.

Many theories have been advanced by the experts of our day to explain why the violins of the famous old masters so far excel the best products of modern workshops. One of these theories is to build the instrument in such a manner that not only the strings, but the body itself shall be under tension. While many inventors have attempted to put this theory into practice, it appears that but one of them has succeeded. Mr. Louis H. Hall, of Hartford, Conn., who was granted a patent covering his construction in 1900, has according to many experts solved the problem. Briefly, Mr. Hall's method consists of cutting the upper and lower tables so that they do not quite fit upon the blocks, and then to force them into proper position under great pressure, thereby putting the required tensile strain into the body.

Dr. T. Lamb Phipson, the well-known English expert, has declared the violin thus constructed the equal of many of the finest instruments of Joseph Guarnerius. Arthur Broadley, another world-famed English expert and player, has unqualifiedly recommended the instrument. The great virtuoso Ysaye has expressed his interest in the violin, and will procure an example of Mr. Hall's work.

Death of Alphonse Chassepot.

Alphonse Chassepot, inventor of the famous Chassepot gun, is dead. He was the son of an armorer, of Mutzig, and followed his father's trade, entering the French state factories and being transferred to Paris in 1858, where he soon became head of the establishment. He studied the Prussian rifle and perfected it, giving his name to the new weapon, which was first used in Italy against the Garibaldians. It has since been abandoned for a more perfect style of rifle. Chassepot received the cross of the Legion of Honor in 1866.

THE QUEEREST OF CREATURES.—II.

BY J. CARTER BEARD.

(Continued from page 11, January 7.)

Among the puzzling adaptive resemblances of lemurs to animals quite low in the scale of animated existence, few, perhaps, are more curious and interesting than those developed by the Lemurid called by the well-known naturalist Cuming the Malmag (*Tarsius spectrum*), which in its adaptation to the exclusively arboreal life common to all but one species only of the Lemuroidæ has achieved a most singular approach in form and in habit to a tree toad.

The absence of any perceptible neck, the short body shaped like a lemon, the grotesquely elongated hind legs and slender ankles of the creature, peculiarities it shares with the batrachian, form an adaptive parallelism that is completed by the button-like pads at the ends of its long fingers and toes, in form and function apparently answering to those which enable the tree toad to cling securely to the upright trunk of a tree or even to the under side of a projecting bough. The lemurs are the only mammals now existing that possess such peculiarly-formed digits.

Indeed, it may well be believed that were it not for its long tail and its ears, and the fact that it is covered with fur, it might, as it hops about in its leafy retreats, be easily mistaken for a specimen of some very large species of Hylidæ. This curious little creature can now be considered as having been adopted by Uncle Sam, and of making one among the many odd specimens of living beings lately added to our fauna, for it is an inhabitant, among other places, of the Philippine Islands.

But the Lemuroidæ have taken ideas and suggestions from the bird as well as from the reptile and from the batrachian.

There are several species of trim, very pretty, very active, and very clever little lemurs called Cheirogales, which build their nests, not at all like those of squirrels, mice, or other so-called nest-building mammals, but nests in every way resembling those of birds, constructed of small, flexible twigs, leaves, and tendrils, with a depression in the center in which, upon a bed of soft hair, are born their naked nestlings, that are fed, protected, and cared for exactly as are those of birds, until old enough to venture out into the world to seek their own fortunes. The smallest of these dainty little creatures is called by the French *le rat de Madagascar*, a name that certainly cannot be said to do them justice. They might with more propriety be called jeweled-eyed lemurs, for they have probably the most resplendent eyes of any living mammal; the tapetum is so large and reflects so much light in the dusk, that the cheirogale appears to possess a pair of magnificent opals for organs of vision.

They are interesting also because of the peculiar habit they indulge in of sleeping through the hottest and driest of the summer months, as many of the mammals in colder climates hibernate in the winter. It is rather remarkable too that they seem to have hit upon the same expedient to lay up a store of nutriment, to be drawn upon when required, as the Syrian sheep (*Ovis aries steatopyga*) at the base of their tails.

Domestication has rendered the fat tails of the sheep of use to their masters only, but the fat-tailed cheirogales depend entirely upon their caudal appendages for sustenance during their long summer fast. They sleep in their nests, and as they retire to them to begin their æstivation, the bases of their long tails are swollen and bulbous; but when they leave their nests at the beginning of the rainy season in Madagascar, they are, both tail and body, emaciated to the last degree.

The little animals are but four inches long, but their tails are fully two inches longer than their bodies. The character of dentition, usually of such specific and distinctly defined methods of arrangement in mammals as to form a reliable basis upon which to build a judgment of family, genera, and species, is among the Lemurids very erratic. One member of the

A WANTIBO (*PERODICTICUS CALABARENSIS*).

group, for instance *Chyromys Madagascariensis*, the aye-aye, exhibits exactly the dentition properly belonging to the order of gnawers, the rodents, and on account of this peculiarity was placed by Buffon among the jerboas or jumping mice; by Cuvier among the squirrels (although he afterward spoke of it as a doubtful animal); and by zoologists generally up to the time of Owen, among rats and beavers as an undeniable rodent. Its physical structure, however, apart from its adult dentition, proves it to be a lemur which has appropriated an adaptive suggestion from another order of mammals. The grotesque and excessive specializations exhibited by the Lemuroidæ are far too

numerous to be indicated here; to do justice to these, and to describe the strange habits of the different members of the group, although so little is yet known of many species, would require a volume which, if properly written, could not fail to prove a most interesting one. Every peculiarity of every species has a meaning and a history of its own, which if justly worked out might go far to determine the inter-relation of laws by which the same environment has produced such widely varying results.

Whatever the nature of the force that, working so differently in different members of the lemuroid group of animals, adapts them all so completely and so perfectly to the same surroundings, the trend of the progress made is surely, however slowly, toward the final destruction of the order; for specializations, in proportion to the extent to which they are carried, unfit the animals specialized to survive changes of environment, of climate, food supply, means of escape from dangerous enemies, and disease-breeding conditions, often too subtle to be defined.

While the lemur, at the foot of the order of Primates, has been the most plastic of the three groups of mammals which constitute it in yielding to this force, impelling toward extreme specialization, man has of all mammals most stubbornly and successfully resisted it, and has in consequence become the most cosmopolitan of animals.

Much difficulty, up to the present day, has been experienced in obtaining live specimens of the Lemurids, but the situation since the protectorate established by France over Madagascar and the incursion of scientific naturalists into the wilder parts of Asia and Africa, no longer presents the insurmountable obstacles which formerly attended any attempt to study the rarer species. Specimens are obtained, and the untiring energy of Mr. W. T. Hornaday, seconded by his colleagues, has already succeeded in placing a number of these curious animals on exhibition, which, notwithstanding their somnolence, are well worth a visit to the New York Zoological Park or to other collections of living animals in other cities where they are to be found. Lemurs are well worth the careful attention that is now being given them, both with respect to their physical structure and their habits.

If the theory of evolution is accepted, it cannot fail to convince the student that we have in this order of animals survivals of extremely ancient types of mammals—types, it is interesting to believe, very nearly akin to those from which have arisen all existing families of the order of Primates, which as the reader may remind himself, includes man as well as monkey.


A Prehistoric Cave Dwelling.

A prehistoric cave dwelling has recently been discovered near Winznau, on Lake Lucerne, in Switzerland. The entrance to this cavern has been blocked for ages by the accumulation of falling rocks and earth. Its existence being known, a party of antiquarians had the entrance passage into the cavern cleared of obstructions, and a grotto or series of caves, dating to the Stone period, was laid bare. A fine collection of stone implements, including knives, axes, and spears, gigantic shells rudely ornamented, evidently drinking vessels and dishes, was discovered. In one chamber of the cavern the explorers found the remains of the bones of many extinct animals; while one section of the cave, which is believed to have been the dwelling of an important family in the Stone age, had evidently served as a workshop for the stonecutters, for here were found many stones in the process of being shaped into implements.

SPECTER TARSIVS (*TARSIVS SPECTRUM*).

AN IMPROVED HAY RACK.


A number of attempts have been made to devise a hay rack which can be fully loaded from a mechanical loader without requiring that the hay be pitched manually from the loading end to the other. The hay rack illustrated in the accompanying engraving is arranged to effect this result in a very convenient and simple manner. It comprises a main frame, formed with boards running longitudinally along each side, and a movable platform mounted on rollers, *A*, which travel on these boards. At the rear or loading end of the hay rack is a vertical abutment attached to the main or stationary frame, and at the other end is a similar abutment attached to the movable frame. Supported on the central post of this abutment is a windlass, from which a cable passes under a pulley, *C*, to the front of the hay rack, where it is secured to a bracket mounted on the main frame. By winding up this rope the movable platform may be drawn to the front of the hay rack. The pulley referred to is mounted in a swinging bracket, which is pivoted to the movable frame. A projection on this bracket is adapted to normally engage one of the cross-bars of the main frame, to prevent the platform from moving forward. But when the windlass is operated, the frame is first drawn up until the crossbars are cleared, after which the forward movement of the platform begins. In use the platform is moved to the rear of the rack, and as soon as the space between the abutments is filled the platform is moved forward, carrying the hay with it, and thus opening a space for further loading. A step is provided on the moving platform for the operator to stand on. The windlass is mounted on a frame which can be attached to the forward abutment at any point suited to the convenience of the operator. Mr. John A. Beierschmitt, of Fairbank, Iowa, is the inventor of this improved hay rack.

**AN IMPROVED HAY RACK.****DETAILS OF THE LOCKING DEVICE.**


lower recess, permitting the forward end of the fender to drop to the track, on which it will be supported by rollers. In this position it is obvious that a person struck by the fender may fall therein without danger of injury. Mr. Louis A. Bechtel, Jr., of Benwood, West Virginia (P. O. box 134), is the inventor of this improved fender.

A SIMPLE CAR FENDER.


The car fender which we illustrate in the accompanying engraving is a very simple contrivance, which may be readily applied to a car of ordinary construction. The connection between the car and fender is such that the latter may be quickly detached from one end of the car and attached to the other end when desired. The fender is also so arranged that its forward end will be normally held a considerable distance above the street surface, but upon striking a person or other obstruction it will quickly fall to safety position. The hangers on which the fender is supported are each formed with two hook members, and between these the side bars of the fender pass. The hook members are each formed with two sockets or recesses, one above the other, adapted to receive the top cross-bar of the fender. Normally, this bar is supported in the upper recesses, as shown in the illustration, and the forward end of the fender is held clear of the street by a pair of locking arms, which engage a plate secured to the under side of the car platform. A hook member on this plate prevents the fender from being moved forward, but by pressing the fender back the locking arms can be disengaged from the plate and the fender removed. When the fender encounters an obstruction, it will thus move back, and the top bar will fall into the

**A SIMPLE CAR FENDER.****A NEW TYPE OF ELECTRIC COUPÉ.**

Our illustration shows a new type of electric coupé

**A NOVEL GRAVITY RAILWAY SYSTEM.**

invented by W. H. Douglas, of Belleville, N. J., and which is now being built by Healy & Co., well-known carriage builders of New York. The machine has two novelties, namely, steering and driving by the front wheels and a new form of steering gear. As the picture shows, the motors are suspended from the front axle and drive, through universal joints, the pinions which work within the internal gear rings attached to the wheels. The rings containing the internal gear teeth are mounted within the outer rings, which are attached to the wheels. The gear rings are arranged to transmit motion received from the pinion through coiled springs to the outer rings. This flexible connection makes the vehicle start very easily and makes the stripping of a pinion almost an impossibility. The new form of steering gear employed consists of two vertical screw-threaded shafts connected together by spur gears. One of these shafts is extended upward to form the steering column on which is mounted the steering wheel. Mounted on the screw-threaded shafts are two nuts, one of which rises, and the other of which descends when the steering wheel is turned. This motion is used to move an inverted L-shaped lever pivoted on the nut on the steering column and having its shorter, or horizontal, leg

**A NEW TYPE OF ELECTRIC COUPÉ.**

slotted near the end to fit over a pin on the nut of the shorter shaft. The long vertical arm of the inverted L-shaped lever is connected to the lever arm on the steering knuckle. This arrangement is absolutely irreversible and will always stay where set.

A NOVEL GRAVITY RAILWAY SYSTEM.

We illustrate in the accompanying engraving a novel railway system invented by Mr. Abraham Abelson, of 109 Henry Street, New York city. This system, as shown, is particularly adapted for crossing rivers, gorges, ravines, and the like, and is designed to effect an economy over existing systems of transportation. It consists of a tower at each anchorage built of skeleton framework, in the center of which an elevator operates. Cables are suspended from a cradle at the tower top and anchored near the base of the opposite tower. Pivoted counter-weights are provided, which serve to keep the cable taut and to compensate for any variations in cable lengths. These weights also remove the lateral pressure on the towers, producing instead a downward pressure thereon. The system does not require any elevated approaches to the bridge entrances. The transporter cars are suspended from swivel trucks which travel on the cables. In practice a car is raised by means of the elevator to the top of a tower, the trucks being turned so as to clear the cables. When the top of the tower is reached, the trucks are turned back to normal position, so that on descent of the elevator they will rest on the cables supporting the car. The car thereupon descends by gravity to the opposite tower. The cars are entirely independent of each other, and the speed of the descending car can be regulated at will, thus effecting a saving of time over such systems as employ two counterbalancing cars.

Santos-Dumont is experimenting with a balloon which differs considerably from his preceding airships. Leaving aside the question of steering, he wishes to obtain a constant altitude for the balloon without loss of gas or ballast under all circumstances, and his new balloon is designed especially to make a long stay in the air. It is of a novel form, consisting of an oval-section balloon which carries a flat framework below it. The balloon body measures 62 feet long and 48 feet in diameter. The *nacelle* is to be hung from the framework. A second balloon or bag is attached to the frame and projects up inside the main balloon, forming a pocket containing 5,500 cubic feet. The pocket is to be supplied by a petrol heater which is carried below. The hot air bag will thus give an added ascensional force which can be varied at will so as to regulate the height of the balloon. The first trial with the new system will bear upon the operation of the heater and the effect of the hot air upon the material of the balloon. If these are successful, he expects to make an ascension later on.

RECENTLY PATENTED INVENTIONS.

Of General Interest.

HAT-FASTENER.—L. VEINDER, New York, N. Y. The intention of this improvement is to provide a fastener, more especially designed for fastening ladies' hats in position on the head and arranged to permit the wearer to conveniently place the hat in proper position, and to then fasten it securely to the topknot of the hair without disturbing the position of the hat and to allow the wearer to readily open the fastener whenever it is desired to remove the hat.

GAGE AND MARKER FOR GARMENTS.—A. WATERMAN and R. WATERMAN, New York, N. Y. The object of the present invention is to so construct the device that the marking-arm will be capable of vertical, horizontal, and swinging adjustment, thus enabling the arm to be accommodated to different characters of work, and especially for marking skirts in such manner that a hem may be evenly turned up at the bottom of the skirt, having either plain or fancy finish, and to render the adjustment such that the marking-chalk be under complete control of the operator. It improves upon and simplifies the construction for which former Letters Patent were granted to A. Waterman.

PENCIL-HOLDER.—W. SCHARRATH and F. A. ROJAS, New York, N. Y. The object in this instance is to provide a holder arranged to permit the user to conveniently attach it to a finger and to move it into any desired position thereof or for moving the holder while on the finger into non-use position to permit the user to conveniently employ the hand for wrapping, tying, and other purposes, the holder being arranged for convenient attachment to a pocket or other part of a garment for supporting the pencil when not in use, the holder also serving as a paper clamp for fastening loose sheets of paper together.

TEMPORARY BINDER.—L. T. PRUDON, North Bergen, N. J. The invention relates to a binder for use on loose-leaf ledgers, memorandum-books, and analogous purposes. The objects are to provide a binder which may be readily locked in a closed position and readily unlocked and opened by a simple movement of a lever which will securely hold the leaves in position.

MOVING DISPLAY-SIGN.—T. B. POWERS, New York, N. Y. In this patent the invention has reference to moving display-signs, Mr. Powers' more particular object being the production of an efficient sign of very attractive appearance, and in which intelligible characters may be displayed in a variety of ways, affording certain advantages. It may be used for election purposes, for advertising, and for bulletin-work.

LIQUID-RIPENER.—A. JENSEN, Topeka, Kan. In the present patent the invention is in the nature of a device for agitating and cooling or heating liquids—as, for instance, in ripening cream preparatory to churning it; and it consists in the novel construction and arrangement of receptacle with means for cooling or heating the cream, as may be desired, and at the same time agitating it. Mr. Jensen has also procured another patent on the same subject which is an improvement in construction, and is in the nature of a device for cooling or heating and simultaneously agitating liquids.

CANDY-HOLDER. J. JEFFERS, JR., Saginaw, Mich. One object of the invention is to provide a receptacle for holding candy or other similar articles, which will automatically close the opening through which the contents are passed and securely hold the same closed until it is desired to remove such contents. Another, is to provide such receptacle which can be opened as readily in darkness for removing contents as in the light.

UMBRELLA.—A. KORTENBACH and K. WÖRNING, Weyer, Rhineland, Germany. The objects in this invention are, to so reduce the upper part of the tubular metal stick in diameter in several steps that it tapers to the end; to apply the umbrella-notch to one of the steps of the stick; to provide the thin end of the stick with a female screw-thread; to provide a screw-threaded top piece which engages in the female screw-thread of the stick; to provide a conical metal tube secured on the top piece and inclosing the reduced part of the stick down to a point near the notch; and, to provide a conical cap for securing the wide end of the conical metal tube on the stick and leading up to the flanges of the notch.

CHAIR.—W. D. JONES, Butler, Pa. This invention refers to improvements in folding chairs, particularly adapted for use in theaters, halls, and the like, the object being to provide a chair so arranged that the seat and back may be closely folded together and turned laterally when not in use, so as to provide spaces or aisles between rows of chairs along which people may readily pass.

FAUCET.—A. E. ISAACS, New York, N. Y. The purpose of the improvement is to provide an effective form of faucet having inlets for hot and cold water, a chamber in which the two may be mingled, and a single outlet. The particular construction relates to the expeditious and convenient manner in which through the manipulation of a single handle the supply of hot or cold water or the combined supply of both may be turned on, regulated, or shut off.

SEALING DEVICE.—C. F. HADT, Indian-

apolis, Ind. In the present patent the invention has reference to devices for sealing such gummed wrappers as envelopes. The principal objects of the inventor are to provide a convenient implement which will simultaneously moisten the gummed portion and press the parts together.

CALK.—F. F. HEISELMANN, Cincinnati, O. The invention refers to calks, and more particularly to those adapted for use in connection with horseshoes. Its principal object is to provide such a device which will be strong and durable and may be readily applied to the shoe and easily replaced when they are worn out. The calks being very resistive of wear will last for a long time.

CLOTHES-PIN.—J. S. BANKS, Portsmouth, Va. This improvement relates to clothes-pins such as used to suspend clothes upon a line to dry. The object is the production of a device of this class which is very simple in construction and which may be readily applied to a line at any point, operating effectively to support the clothes which may be attached thereto. The device is preferably to be formed of wire.

CIGAR-PERFORATOR.—C. BLUMER, Guttenburg, N. J. The object of the improvement is to provide a perforator more especially designed for penetrating the sides of the cigar at or near the point thereof to provide draft-holes for drawing the smoke through, the arrangement being such that the wrapper is not loosened or unraveled when forming the draft-holes by the instrument.

OPTICAL TOY.—M. ABRAMOWITZ, New York, N. Y. The device being held in one hand and the eye applied to the eyepiece and an illuminated scene or object viewed this becomes visible, multiplied by the facets and of the color of the eyepiece. Moreover, because of prismatic refraction there is also seen a plurality of spectra, and upon rotating the eyepiece by means of the operating member both the objects and spectra revolve, producing a most attractive effect.

RESPIRATOR AND INHALER.—G. N. GUTHRIE, JR., Cookeville, Tenn. Mr. Guthrie's invention is attached to the face in order to permit the subject to breathe air from other rooms or purified air and prevent inhaling of undesirable gases and vapors. His objects are to provide inhalers and respirators with devices for purifying air, removing solid matter therefrom, and for conveniently connecting them to such purifying devices or to outside air. It is capable of universal use and attachable to any subject, being made in various sizes. It is light, inexpensive, prevents air from entering the lungs except through the filtering medium, permits no rebreathing of exhaled air, and is not likely to become clogged.

Heating and Lighting.

HEATING APPARATUS.—N. M. EDDY, Alpena, Mich. The purpose in this case is to so construct the air-escape valve for heating apparatus that but one valve is required in the length of the air-line for the entire apparatus and so that the valve will be simple and not liable to be affected by heat, and, furthermore, to so construct the valve that it will greatly add to the speedy and economic operation of the heating system in connection with which it is used, permitting air to readily escape, but positively preventing a return of the air through atmospheric pressure.

Household Utilities.

SCREEN-FASTENER.—C. W. GREENE, Brown Valley, Minn. The purpose of this invention is to provide a fastening device which can be expeditiously secured in a casing and which may remain therein when the screen or the storm-sash is removed and also to so construct the device that it will be provided with a spring retaining-arm capable of being quickly and readily brought to a bearing against the frame fitted in the casing.

SWINGING SLIDING DOOR AND MEANS FOR SUSPENDING SAME.—R. H. JONES, Portland, Ore. The class of sliding doors provided for houses, barns, stables, warehouses, etc., is improved by this invention, so that when duly adjusted in position for closing the entrance they may be swung laterally in the same way as a hinged door. In other words, the improved door and attachments are adapted to be slid longitudinally for opening and closing the entrance and also enable it to swing on a pivot-support, so that the entrance may be opened without sliding the door.

Machines and Mechanical Devices.

PUMP-ROD LIFTER.—T. H. TREGELLAS, Inka, Kan. In this device hanger bars are carried by a clevis to which a draft rope is connected, and at the lower end the bars carry a gripping dog to which a bail is pivoted. The bail and arms slide downward on the pump rod when the rope is slackened and an upward pull on the rope causes the pump rod to be gripped between the dog and the inner surface of the bail whereby the rod may be readily drawn upward.

DYEING-MACHINE.—J. LEISEL, Charlotte, N. C. The object of the invention is the provision of a machine arranged to keep the material submerged, to prevent the material from coming in contact with the air during the dyeing operation, to carry on the dyeing operation

economically both in time and labor, to expedite unloading of the machine after material is dyed, and to remove foreign and insoluble matter from the dyeing liquor during the process of dyeing, to facilitate circulation of the dyeing liquor through the material, and to prevent uneven and spotted shades in the dyed material.

Railways and Their Accessories.

AUTOMATIC RAILROAD-SWITCH.—G. CURRIER, St. Paul, Minn. Mr. Currier's invention is in the nature of a switch designed more particularly for rapid-transit street-railways, but applicable also to all kinds of railways. It relates to that form of railroad-switch in which the switch is connected to and operated by a movable device in the road-bed which is struck by a projection on the car as it passes over the device, whereby the switch is automatically adjusted by the passage of the car without having to stop and adjust the switch by hand.

RAILWAY-SWITCH.—E. G. MICK and J. M. GILLILAND, Newcastle, Pa. In the Messrs. Mick and Gilliland invention the improvement is in railway-switches. As the train passes from the siding onto the main track the switch opens automatically by the pressure of the flanges of the wheels, permitting the train to pass through the switch onto the main line. In this operation as the train comes from the siding passing onto the switch-rail the flange of the wheel will force the rails into position to permit the train to pass onto the main track and also operate the pressure-bar in moving thereon.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.** MUNN & CO.

Marine Iron Works, Chicago. Catalogue free.

Inquiry No. 6551.—For manufacturers of machines for desiccating coconuts and other neeces any machinery for a coconut plant, as slicing, shredding, grating, etc.

"U. S." Metal Polish, Indianapolis. Samples free.

Inquiry No. 6552.—For makers of paper tape, such as used in stock machines, telegraph instruments, etc.

Perforated Metals, Harrington & King Perforating Co., Chicago.

Inquiry No. 6553.—Wanted, a machine for perforating pianola music rolls.

Handle & Spoke Mch. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

Inquiry No. 6554.—For makers of marine engines, h. p. from 20 to 300 single, compound and triple explosion.

Adding, multiplying and dividing machine, all in one. Felt & Tarrant Mfg. Co., Chicago.

Inquiry No. 6555.—Wanted, a machine for cutting out envelopes.

Sawmill machinery and outfits manufactured by the Lane Mfg. Co. Box 13, Montpelier, Vt.

Inquiry No. 6556.—For manufacturers of sheet iron or steel powder kegs in which blasting powder is usually shipped.

Robert W. Hunt & Co. bureau of consultation, chemical and physical tests and inspection. The Rookery, Chicago.

Inquiry No. 6557.—For the address of the manufacturer of Golden's all metal weather strips; or for makers of any other weather strips.

If you wish to buy patents on inventions or sell them, write Chas. A. Scott, 719 Mutual Life Building, Buffalo, N. Y.

Inquiry No. 6558.—For apparatus for making and burning charcoal.

We manufacture anything in metal. Patented articles, metal stamping, dies, screw mach. work, etc. Metal Novelty Works, 43 Canal Street, Chicago.

Inquiry No. 6559.—For a machine for sifting sand and gravel, also for lifting the same into cars at height of 20 to 30 feet.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Machine Company. Foot of East 138th Street, New York.

Inquiry No. 6560.—For makers of the silver or "G" strings for violins, guitars, mandolins, banjos, etc.

The SCIENTIFIC AMERICAN SUPPLEMENT is publishing a practical series of illustrated articles on experimental electro-chemistry by N. Monroe Hopkins.

Inquiry No. 6561.—For makers of woven wire pillows.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, machinery and tools. Quadriga Manufacturing Company, 16 South Canal Street, Chicago.

Inquiry No. 6562.—For manufacturers of persulphate of ammonia.

VALUABLE U. S. PATENT FOR SALE.—I will dispose of the American rights of my Patent Thill. A necessity for farmers and drivers. Price reasonable. Address Harry Turner, Koolunga, South Australia.

Inquiry No. 6563.—For a plant and machinery for manufacturing starch from cassava.

WANTED.—Revolutionary Documents and Autograph Letters, Prints, Washington Portraits, Eighteenth Century Illustrated Magazines and Books, Early Patents signed by Presidents of the United States. Valentine's Manuals of the early 40's. Correspondence solicited. Address C. A. M., Box 773, New York.

Inquiry No. 6564.—For manufacturers of home illuminating outfit, also wood-burning furnace.

I have every facility for manufacturing and marketing hardware and housefurnishing specialties. Wm. McDonald, 190 East Main St., Rochester, N. Y.

Inquiry No. 6565.—For machinery for square self-opening paper bags.



HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(9540) J. L. C. says: Which of either brass, iron, tin, steel, copper, or aluminium is the most affected by temperature, and what will its expansion be with a change of 60 deg. on a Fahrenheit thermometer? A. Tin has the highest co-efficient of expansion of the metals you name. A bar of tin 100 feet long will expand 0.87 inch if the temperature is increased 60 deg. F. Lead will expand 1.14 inches, and a mixture of one part tin and two parts lead (white solder) will expand 1 inch under the same circumstances.

(9541) B. B. B. asks: Under the conditions stated in query No. 9513 in your issue of December 31, 1904, if a gun is discharged in the rear of a train traveling one mile a minute—the bullet speeding one mile a minute in the opposite direction from which the train is going—will the bullet leave the muzzle of the gun? If in query 9513 the bullet gathers momentum from the train, why will not the momentum overcome the speed of the bullet? A. A bullet will certainly leave the gun under the conditions stated in query 9513. The expansive force of the gas will carry the bullet out of the gun. This expansive power is evidently not affected by the motion of the train. It is this which produces the motion of the bullet in the direction opposite to that of the train. When the backward motion produced by the gas reaches one mile a minute, the ball will come to rest so far as a point on the earth under the ball is concerned. The ball can only get a mile a minute forward from the train. It gets a mile a minute backward from the powder. The two are equal.

(9542) F. B. M. says: We have our own electric outfit. We have a switchboard with ammeter and voltmeter. We carry 110 volts, but the lights are much dimmer than our city lights, whose voltage is only 104. How can I determine whether our voltmeter is correct or not? I believe it is very far from being correct. A. The easiest way to settle the comparative readings of your voltmeter and that of the city plant is to take one of the instruments to the other plant and compare the two on the same line. Another way would be to connect the voltmeter which is suspected of being in error to a storage battery of known voltage. There is no way of testing an instrument without a standard of some sort. If there is no standard nearby, you can send it to the manufacturer and have it put in order. During its absence you may be able to get along by regulating the current till the lamps are of a proper brightness.

INDEX OF INVENTIONS


For which Letters Patent of the United States were Issued for the Week Ending

February 14, 1905

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Acid, analogous derivatives, and making them, dipropyl-barbituric, E. Fischer..	782,740
Acid and making same, C-C-dialkyl-barbituric, E. Fischer	782,739
Acid and making same, disubstituted barbituric, E. Fischer	782,741
Acids and making same, trisubstituted barbituric, E. Fischer	782,742
Adjustable chair, J. Harvey	782,335
Advertising apparatus, illuminated, A. H. Trimm	782,370
Agricultural implements, change speed gearing for, C. H. Pelton	782,579
Air compressor equalizing mechanism, E. Cheshire	782,597
Air lock, C. Campus	782,596
Alloy, metallic, L. H. E. Lacroix	782,401
Amalgamator, M. V. Lasswell	782,611
Ammonium sulfate saturator, K. Zimpell	782,637
Anchoring device, tractor, A. Castellan	782,643
Angle joint, interlocking, S. R. Bailey	782,639
Armature windings of dynamo electric machines, conductor for the, C. A. Parsons	782,463
Auger bit, P. J. Creeden	782,221
Automobile controller, E. N. Dickerson	782,548
Awning pole mounting, M. F. Wiedemann	782,300
Axle, L. A. Keene	782,564
Bag, See Feed bag.	
Bag holder, W. Downie	782,439



CADILLAC

The Car of Economy

The greater your familiarity with automobiles in general, the greater is your appreciation of the many surpassing qualities of the Cadillac.

In no feature is Cadillac superiority more pronounced than in economy of maintenance—a motor problem which, until we entered the field, remained unsolved. The simple, durable, common-sense construction of the Cadillac, its perfect self-adaptability to the various exigencies of automobile travel, make it by far the most economically maintained of all motor cars.

Absolute dependability and safety of operation under all conditions are insured in the Cadillac by its wonderful ease and simplicity of control, for neither the motor nor its connections can in any way be deranged through a mistake in manipulation. By a single, almost unnoticeable, movement of the driver's hand, the speed of the car, though it equal that of an express train, may within a few feet be reduced to a mere snail-pace.

The illustration above shows our new Model F touring Cadillac, a car of almost incredible power and endurance, embodying all that could be desired in appointment, elegance of design, excellence of construction, comfort of riding. These same surpassing qualifications are manifest in the other models.

All Cadillac engines are built after our own exclusive designs by makers acknowledged to be the best in America. This is the secret of the marvelous power of "the car that climbs."

Model F—Side-Entrance Touring Car, shown above, \$950.

Model B—Touring Car, with detachable tonneau, \$900.

Model E—Light, stylish, powerful Runabout, divided seat, \$750.

Model D—Four-Cylinder, 30 h. p. Touring Car, \$2,800. The marvel of the automobile world.


Write for catalog N, and address of nearest dealer, where you can see and try a Cadillac.

CADILLAC AUTOMOBILE CO., Detroit, Mich.


Member Association Licensed Automobile Manufacturers.



Model E



Model D



Model B

"Star" Lathe Foot and Power Screw Cutting

Automatic Cross Feed

FOR FINE, ACCURATE WORK

Send for Catalogue B.

SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

ENGINE & FOOT MACHINE SHOPS OUTFITS

LATHES TOOLS & SUPPLIES

SEBASTIAN LATHES CO. CINCINNATI, O.

Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.

SHEPARD LATHES CO., 133 W. 2d St. Cincinnati, O.

GIANT STEAM SHOVELS

Toledo Ohio, U.S.A.

The Vulcan Iron Works Co.

MOTORS

We furnish castings for eight different motors, air or water-cooled. Also complete motors for all purposes. Largest Motor Cycle House in the World. Send two cents in stamps for our 150-page catalogue.

THE HARRY R. GEER CO.
1015 Pine St., St. Louis, Mo.

8 LIGHT DYNAMO \$26.50

Other sizes 3 to 300 Lamps

MOTORS

from 1-16 to 20 H. P.
Write for Bulletin

RUTH BROS. & CO.
22 S. Clinton St., Chicago

FOR GUNSMITHS, TOOL MAKERS, EXPERIMENTAL & REPAIR WORK, ETC.

From 9-in. to 18-in. swing. Arranged for Steam or Foot Power. Veldoped or Stand-up Treadle.

Send for Lathe Catalogue.

W. F. & JNO. BARNES CO.
Established 1872.
1999 Ruby St., Rockford, Ill.

THE EUREKA CLIP

The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by Consolidated Safety Pin Co., Box 121, Bloomfield, N. J.

MAXIMUM POWER—MINIMUM COST

If you use a pump for beer, lard, acids, starch, petroleum, brewer's mash, tanner's liquor, cottonseed oil or fluids, hot or cold, thick or thin, you want to get the **TABER ROTARY PUMP** which does the most work at the least expense. Simply constructed. Can be run at any desired speed. Perfectly durable. All parts are interchangeable. Needs no skilled workman. Details guaranteed. Catalogue free.

TABER PUMP CO., 32 Wells St., Buffalo, N. Y., U. S. A.

If You Want the Best Lathe and Drill CHUCKS

BUY WESTCOTT'S Strongest Grip, Greatest Capacity and Durability, Cheap and Accurate.

Westcott Chuck Co., Oneida, N. Y., U. S. A.
Ask for catalogue in English, French, Spanish or German.
FIRST PRIZE AT COLUMBIAN EXPOSITION, 1893.

LUFKIN TAPES AND RULES

ARE THE BEST.

For sale everywhere. Send for Catalogue No. 16.

LUFKIN RULE CO.
Saginaw, Mich., U. S. A.
New York and London.

EVERYTHING FOR THE AUTOMOBILE

YANKEE GRADE-METER

Price \$7.50

Gives the grade accurately up to 40 per cent. up and down. Easily read from the seat.

Yankee Mica Spark Plug
Closed End, \$1.50
Open End, 1.00
Both guaranteed 90 days

BIG FREE CATALOG

E. J. WILLIS CO., 2 Park Place, N. Y.

WELL DRILLING Machines

Over 70 sizes and styles, for drilling either deep or shallow wells in any kind of soil or rock. Mounted on wheels or on skids. With engines or horse powers. Strong, simple and durable. Any mechanic can operate them easily. Send for catalog.

WILLIAMS BROS., Ithaca, N. Y.

Band cutter and feeder, P. G. Gifford...	782,497
Bath tub pattern, F. D. Cook...	782,776
Bearing for armature shafts, antifriction, Ward & Buchheit...	782,474
Bearing, roller, J. A. Liddback...	782,347
Bearings, yoke and hardened steel collar for marine thrust, C. W. Thorn...	782,768
Belt, driving, C. E. Becker...	782,479
Belt shifting device, machinery, J. H. Moore...	782,350
Bending machine, A. G. Scherer...	782,361
Bicycle stand, J. G. Johnson...	782,664
Binding loose or folded sheets of paper, etc., Searies & Shearer...	782,420
Bit, W. B. Swan...	782,368
Blower, J. McKone...	782,355
Bobbin holder, G. A. Clark...	782,487
Boiler, Q. N. Evans...	782,737
Boiler flue cleaner, F. W. Jackson...	782,608
Boiler patch, S. D. Tompkins...	782,290
Boiler sediment collector, H. H. Baltzley...	782,314
Boiler superheater, steam, F. J. Cole...	782,489
Boiler superheater, steam, Cole & Mellin...	782,490
Boiler tube detaching tool, H. A. Poppenhusen...	782,523
Bolts, etc., manufacturing, J. L. Replogle...	782,467
Book, H. H. Hill...	782,246
Bookbinding, L. Streit...	782,365
Book construction, H. H. Hill...	782,247
Book, insertible leaf record, M. C. Neuner...	782,413
Book or album, blank, J. R. Staples...	782,286
Books, machine for making end papers for, F. H. H. Hoffstedt...	782,750
Books, removable cover and holder for pass and sales, F. L. Winters...	782,476
Bottle, J. W. Potter...	782,695
Bottle and stopper therefor, A. J. Swain...	782,704
Bottle closure, W. H. Sheffield...	782,757
Bottle closure, T. F. Odell...	782,305
Bottle clutch, A. Wolfensberger...	782,268
Bottle, non-refillable, J. L. Prior...	782,477
Bottle, non-refillable, O. Yates...	782,640
Bottle, non-refillable, W. M. Barry...	782,653
Bottle, non-refillable, W. Handler...	782,758
Bottle, non-refillable, C. J. Paulson...	782,780
Bottle stopper, E. P. Dole...	782,762
Bowling alley or game apparatus, L. A. Scholz...	782,289
Box, W. E. & D. M. Taylor...	782,528
Box fastener, E. J. Steward...	782,426
Box machine, cylindrical, W. H. Stout...	782,416
Brake, Quintano & De la Cuesta...	782,599
Brake beam, F. R. Cornwall...	782,526
Brake shoe for wagons, etc., C. B. Siner...	782,514
Braking system, electric, C. A. Mudge...	782,324
Brick cleaning machine, M. T. Christopher...	782,602
Brick making apparatus, J. Draenert...	782,766
Brick making, mixer and feeder for use in, E. D. Steger...	782,215
Bridge, C. Bryant...	782,216
Bridle bit, G. Cairn...	782,470
Briquet machine, R. Schor...	782,621
Broom head, W. P. McMahon...	782,580
Brush, W. Reese...	782,530
Brush, paint, C. W. Swanson...	782,423
Buckle, G. Shoenberger...	782,810
Building construction, Murphy & Camp...	782,613
Burglar alarm and door or window check, combined, C. P. Logan...	782,309
Button forming machine, collar, E. J. Yale...	782,687
Button, self-fastening, E. Noelle...	782,234
Button, separable, J. Gibson...	782,307
Cable terminal, C. R. Sturdevant...	782,363
Caisson or carrier, J. W. Doty...	782,554
Calculating machine, H. E. Goldberg...	782,492
Calendar, perpetual, J. M. Crawford...	782,649
Camera, J. Goddard...	782,333
Camera finder, A. O. Graf...	782,432
Can. See Oil can.	782,610
Can body making machine, J. Anderson...	782,630
Car construction, metallic, G. I. King...	782,265
Car door, W. C. Norman...	782,805
Car fender, R. Andlauer...	782,407
Car friction draft gear, railway, W. H. Miner...	782,408
Car friction draft rigging, railway, W. H. Miner...	782,794
Car friction draft rigging, railway, P. N. Moore...	782,793
Car lifting apparatus, street, C. Churilla...	782,598
Car or train signal, W. Lintern...	782,454
Car or wagon, dumping, C. Erickson...	782,807
Car self-coupling device, railway, H. de Castro...	782,724
Car signal system, W. Lintern...	782,455
Car, steam motor, J. A. & J. M. B. R...	782,624
Car unloading machine, J. G. Helmechen...	782,337
Car wheels to their rails, device for fastening, A. J. Eddins...	782,647
Cars or logging sleighs, stake for, Lewis & Bostwick...	782,257
Carburetor, C. L. Mohr...	782,788
Carburetor, portable, M. Mossig...	782,619
Card punching device for the manufacture of pattern cards, C. Handwerck...	782,499
Card punching machine lashing device, C. Handwerck...	782,500
Carpet beating and brushing machine, J. J. McGrath...	782,620
Carriage top support, J. Hough...	782,504
Carrier automatic extension feeder, L. W. Drogemeier...	782,384
Cart, E. C. Weber...	782,295
Cartridge clip, J. H. Goss...	782,556
Cash register, T. Carroll...	782,217
Casing spear, F. W. Jones...	782,506
Casket, F. E. Hollins...	782,563
Casting pattern, gear wheel, T. W. Lowe...	782,674
Ceiling and wall box, J. T. Robb...	782,417
Cement or concrete catch basins, machine for making, J. M. Phelan...	782,797
Cement roofing and sheathing, J. R. Kelly...	782,507
Cement work, outside form for, C. Gustafson...	782,446
Chart, adjustable dress, H. N. Plant...	782,415
Check strap holding device, F. A. Le Court...	782,784
Cheese cutter, W. G. Templeton...	782,629
Cigar box filler, H. J. Lewis...	782,573
Clay screen, I. H. Ross...	782,581
Clothes line fastener, H. Hubert...	782,657
Clothes line reel, A. Yeager...	782,478
Clothes pin, F. Kirkpatrick...	782,606
Clover buncher, W. A. Williams...	782,301
Coal, etc., means for distributing, J. Campbell...	782,485
Coal scuttle, A. S. Mathers...	782,678
Cock, stop, R. Y. & D. C. Burger...	782,722
Cockeye, E. F. Butler...	782,380
Coffee mill grinding disk, A. A. Warner...	782,293
Coffee or spice mill, A. A. Warner...	782,372
Coffee roaster and mixer, Warner & Mathewson...	782,770
Coffer dam, Moran & Doty...	782,410
Coin controlled mechanism, J. E. Packard...	782,795
Coke oven, retort, C. S. Mason...	782,259
Collar and pad, combined horse, T. R. Massey...	782,616
Column, metal, W. F. Eichfeld...	782,495
Combination lock, A. S. Winston...	782,304
Composition of matter and making it, B. F. Gardner...	782,232
Connection box, E. R. Le Manuais...	782,255
Conveying apparatus, material, H. Marcus...	782,677
Cotton chopper and weed cutter, Simmons & Rose...	782,705
Coupling pipe, J. H. Glauber...	782,552
Crackling press, J. T. Minyard...	782,618
Cultivator and harrow, combined, S. A. Ware...	782,633
Cultivator, listed corn, Simpson & Johnson...	782,281
Cup holder, C. D. Holden...	782,448
Curtain fastener, J. F. Wildgen...	782,712
Curtain pole tip, E. Kirmss...	782,345
Cutter. See Band cutter.	782,625
Decoy duck, Rimpler & Self...	782,223
Delinting machine, R. Derdeyn...	782,627
Dental plate, H. J. Tarr, Jr.	782,319
Disk drill, T. Brennan, Jr.	782,311
Display apparatus, electric, E. L. Zalinski...	782,430
Display cabinet, package, W. E. Toner...	782,346
Display rack for supporting, measuring, and cutting oil cloth or other materials, G. H. King...	782,565
Display support, R. W. Lantz...	782,346

The Improved Method of FINISHING FLOORS

Filling cracks with GRIPPIN'S Filler and Patent Applier

Old or new, for rugs or otherwise, with GRIPPIN'S Wood CRACK and CREVICE FILLER and FINISHING SPECIALTIES, is very simple and economical, not requiring skilled labor though the highest degree of perfection is attained. We give full instructions for treating all surfaces. Write to-day for our descriptive matter to

GRIPPIN MFG. CO.
Dept. 6
Newark New York

A 1000 years of mistakes and then the

Naturo

the closet with a slant, the only sort of construction that is healthy, clean, comfortable. The NATURO is the only improvement made in Water Closets since the style YOU know was conceived. Aren't you interested in knowing "Why?" Write for book L. It tells in detail, with illustrations. **THE NATURO CO., Salem, N. J.**

The "Kickdrive" Forge

costs no more than the common kind, but is very uncommon, as it has a good foot power drive, allowing the operator to devote both hands to his work. Get a booklet.

SLOTKIN & PRAGLIN
210A Canal Street, New York

The Cushman Motor

never disappoints. The least weight for the power developed makes it the Best Boat and Auto Motor on the market. The New 1905 Model is better than ever. The engine proper is valveless. The cylinder, water jacket and head are cast in one piece. It is the simplest as well as the most efficient. Holds many speed records. Made in Single and Double Cylinder patterns. Prices make it economical. Cut shows 2 1/2 h.p. marine, weight 75 lbs. We make Auto Motors and Stationary Engines. Catalog free. Agents Wanted.

CUSHMAN MOTOR CO.
2026 N Street, Lincoln, Neb., U. S. A.

Heals Cuts, Burns, Bruises, Sores, Etc.

CABOT'S Sulpho-Naphthol

LIQUID CLEANLINESS.

At all dealers or 10c. and 25c. pkgs. by mail. Look for above trade mark.

Sulpho-Naphthol Co., 15 Haymarket Square, Boston, Mass.
Sold in N. Y. City by Acker-Merrill, Macy, Siegel-Cooper.

ELECTRICAL MOTORS—THEIR Construction at Home. SCIENTIFIC AMERICAN SUPPLEMENTS 759, 761, 767, 641. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers.

A.W. FABER

Manufacture Established 1761.

LEAD PENCILS, COLORED PENCILS, SLATE PENCILS, WRITING SLATES, INKS, STATIONERS RUBBER GOODS, RULERS, ARTISTS' COLORS.

78 Reade Street, New York, N. Y.
GRAND PRIZE, Highest Award, PARIS, 1900.

Every Mechanic Should Own It.

Montgomery & Co.'s Tool Catalogue which is thoroughly up-to-date. 704 pages and discount sheet. Sent by mail for 25 cents.

MONTGOMERY & CO.,
105 Fulton St., New York City.

A Motor Cycle at Small Cost by using one of Our Attachable Outfits. Also a complete line of Castings and Finished Motors for Bicycle, Automobile, Marine or Stationary. Send 2-cent stamp for catalog

STEFFEY MFG. CO.
2730 Brown St., Phila., Pa.

The LATHROP Portable Fence

Can be constructed by any handy person who buys from us the necessary supports and the right to use our method. Such fencing is strong and permanent, but can be removed or changed at will, to alter size or shape of enclosure. Our plan saves the cost of transportation, as supports only need be sent. The price for supports, with erection rights, is \$1.00 per pair; 5 per cent. discount in 10 pair lots; 10 per cent. in 25 pair lots.

The Lathrop Mfg. Co., 47 Central Av., Rochester, N. Y.

SPECIES AND VARIETIES: Their Origin by Mutation

Lectures delivered at the University of California by **Hugo de Vries**

Professor of Botany in the University of Amsterdam Edited by D. T. MACDOUGAL Ass. Dir. New York Botanical Garden Pp. xviii, 847, 8vo., \$5.00. Send for descriptive circulars and catalogue of books on Mechanics, Mathematics, Biology and Kindred Sciences.

THE OPEN COURT PUBLISHING CO.
1322 Wabash Ave., Chicago

The N-Rays.


SCIENTIFIC AMERICAN SUPPLEMENT 1487 describes some of the more remarkable N-ray phenomena and shows how N-rays may be photographed.

SCIENTIFIC AMERICAN SUPPLEMENT 1491 tells of some extraordinary results obtained with the N-rays.

SCIENTIFIC AMERICAN SUPPLEMENT 1511 contains a skeptical article by Professor Wood on the N-rays and a reply thereto written by Professor Blondlot at the request of the Editor of the SCIENTIFIC AMERICAN.

Each SUPPLEMENT named costs Ten Cents by mail. Order from your newsdealer or from

MUNN & CO. 361 BROADWAY, NEW YORK



PEERLESS Direct Drive TOURING CARS

Combine elegance, simplicity and dependability. Elegantly finished in every detail. Run smoothly and silently and are instantly responsive to control.

Motors of exactly the same construction as those in the famous Peerless "Green Dragon" racing car, driven by Barney Oldfield.

Four forward speeds on all models. The enclosed bevel gear drive transmits full power of the engine to the wheels without loss.

PRICES FOR 1905

24 H. P. \$8,200 30 H. P. \$8,750
35 H. P. 4,000 60 H. P. 6,000

Limousine 4,000 (five passengers inside)

Our 1905 catalogue with detailed description of all models mailed free.

PEERLESS MOTOR CAR CO.
38 Lisbon St., Cleveland, Ohio
Member Association Licensed Automobile Manufacturers.

TOOLS FOR MECHANICS.

Send for Free Catalogue No. 16 B.

The L. S. Starrett Co., Athol, Mass., U. S. A.

DO YOU USE GRINDSTONES?

If so we can supply you. All sizes mounted and unmounted, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. Send for catalogue "I"

THE CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

A MONEY MAKER

Hollow Concrete Building Blocks, Best, Fastest, Simplest, Cheapest Machine.

PETTYJOHN BROS.
1315 N. 1st Street, Terre Haute, Ind.

THE Nulite Vapor Gas Lamps

For Home, Store and Street

We also manufacture Table Lamps, Wall Lamps, Chandeliers, Street Lamps, Etc. 100 Candle Power seven hours ONE CENT. No Wicks. No Smoke. No Odor. Absolutely safe. THEY SELL AT SIGHT. Exclusive territory to good agents. Write for catalogue and prices.

Chicago Solar Light Co., Dept. G, Chicago

\$3.00 Set of castings and parts for the "MODEL" DYNAMO

with drawings and directions for building. Will Run Lights. Charge Storage Battery. Used as a Motor. Will Drive Lathe, etc. Send for Circular.

Waltham Model Supply Co.
WALTHAM, MASS.

Make Money With Hens

You can do it with certainty by using

CYPHERS INCUBATOR

"The World's Standard Hatcher" used and endorsed by 45 Government Stations. Price \$6.50 and up. Complete catalog and poultry guide, 212 pages (8x11 inches), free if you mention this paper. Address nearest office.

Cyphers Incubator Co., Buffalo, N. Y.
Boston, Chicago, New York, Kansas City, San Francisco

The Wooden Hen

and 200 eggs will start you in a pleasing and profitable business raising poultry. Hundreds of men and women make good money raising chicks for early market. Why not you? Write for free catalogue.

GEO. H. STAHL, Quincy, Ill.

Squabs Pay Best Hens

Easier, need attention only part of time, bring big prices. Raised in one month. Attractive for poultrymen, farmers, women. Send for FREE BOOKLET and learn this immensely rich home industry.

PLYMOUTH ROCK SQUAB CO.,
289 Atlantic Ave., Boston, Mass.

Hydrozone

Cures Sore Throat

A Harmless Antiseptic.

Endorsed by the medical profession. Send ten cents to pay postage on **free trial bottle**. Sold by Leading Druggists. Not genuine unless label bears my signature:


Prof. Charles Howard

Dept. U, 63 Prince St., N. Y.

Write for free booklet on Rational Treatment of Disease.

SMALLEY

MARINE GAS ENGINES



POWER FOR YOUR BOAT

SMALLEY marine engines are recognized as standard the world over. A wise man will not attempt to save a few dollars by purchasing questionable goods. Our machine is worth far more to you than we ask you to pay. You get absolute satisfaction and the benefit of the latest practical improvements—not fads. You get the benefit of our long experience in building marine gas engines exclusively. You have the satisfaction of knowing that you are dealing with responsible parties whose guarantee means something. Our 34 page handsomely illustrated 1905 catalogue will be sent on receipt of 10 cents in postage. See our exhibit at Motor Boat Show at Madison Square Garden, N. Y. Address Dept. W.

SMALLEY MOTOR CO., LTD., Bay City, Mich., U. S. A.
Member of the National Ass'n of Engine and Boat Mfrs.

KLIP-KLIP JR.

15c. At your dealers' or by mail.

The most perfect and compact pocket manicure ever invented. Trims, files, cleans perfectly. Simple, strong and durable.



Makes the nails beautiful, round and smooth.

Send for the book how to care for the hands and nails, five 2c. stamps. (The original German silver Klip Klip, 25c.)

KLIP-KLIP CO.,
556 Clinton Ave. S.,
Rochester, N. Y.

THE NEW YORK, CHICAGO & ST. LOUIS RAILROAD COMPANY

PASSENGER DEPARTMENT

Office of the General Agent, Buffalo, N. Y.

THE NICKEL PLATE ROAD BETWEEN NEW YORK AND BOSTON, AND CLEVELAND, FT. WAYNE AND CHICAGO

Lowest rates and elegant equipment makes this a favorite route between the above points. Through sleepers. Unexcelled dining car service. Individual club meals 35 cents to \$1.00 each. Also a la Carte. Full information on application to R. E. Payne, General Agent, 291 Main St., Buffalo, N. Y., or A. W. Ecclestone, D. P. A., 385 Broadway, New York City.

How To Increase Your Business

READ carefully, every week, the **Business and Personal Wants** column in the

Scientific American

This week it will be found on page 169.

Some week you will be likely to find an inquiry for something that you manufacture or deal in. A prompt reply may bring an order.

Watch it Carefully


Distilling apparatus, L. E. Beers.....	782,377
Door and grating, jail, I. Maloch.....	782,787
Door hanger, F. B. Cook.....	782,491
Door locking device, C. W. Bitner.....	782,641
Door, self-closing, F. M. Edmonds.....	782,224
Doubletree, H. D. Le Suer.....	782,402
Draft apparatus, J. G. Brown.....	782,322
Draft rigging, friction spring, J. R. Mitchell	782,409
Draft rigging, friction spring, P. N. Moore	782,790 to 782,792
Drawing instrument, F. E. Jenkins.....	782,662
Drawing table, R. Niemann.....	782,686
Dressmaker's fitting saddle, M. L. Soule.....	782,364
Drier, P. L. Simpson.....	782,282
Drinking glass or like tableware, C. Weller	782,710
Drop light, gas, A. W. Nicholls.....	782,414
Duster, L. M. Lea.....	782,669
Ear muff, H. L. Wallach.....	782,769
Ear ring, S. Zirinsky.....	782,313
Earth boring device, H. L. Zander.....	782,636
Electric cable, A. P. Hanson.....	782,391
Electric controller, H. von Kramer.....	782,450
Electric machines, means for regulation of dynamo, A. S. Hubbard.....	782,340
Electric meter fraud detector, W. W. Fuller	782,386
Electric motor controller, A. C. Eastwood.....	782,732
Electric motors, and controlling the speed of devices actuated thereby, mechanism for operating, O. C. Britsch.....	782,593
Electric system, H. Dowie.....	782,550
Electric time switch, W. H. Gerhard.....	782,387
Electric wire conduit, R. W. Lyle.....	782,576
Electrical distribution and control system, E. Lyndon.....	782,456
Electrical fountain, M. Levy.....	782,612
Electrodes, manufacturing storage battery or accumulator, H. F. Hobel.....	782,656
Electrolytic apparatus, A. Wright.....	782,308
Embossing machine, A. Nicolle.....	782,516
End gate fastening, P. J. Hurley.....	782,660
Engine attachment, explosive, B. Hayden.....	782,502
Engine nozzle, locomotive steam, J. B. Irving.....	782,250
Engine water cooler, explosive, E. F. Hulbert.....	782,659
Ensilage elevator distributor, E. F. Gibbons.....	782,444
Envelope, R. W. King.....	782,344
Envelope, safety, W. E. Hingston.....	782,397
Eyeglasses, M. H. Wolf.....	782,306
Eyeglasses, W. W. Cervantes.....	782,545
Eyeglasses or spectacles, F. A. Stevens.....	782,287
Eyeglasses or spectacles, D. H. Ludlow.....	782,575
Fan, G. W. Davis.....	782,437
Fastener, A. C. Leahy.....	782,670
Fastener, separable, D. L. Watson, Jr.....	782,803
Faucet, F. Gaensslen.....	782,648
Feed and litter carrier, W. & R. B. Loudon.....	782,785
Feed bag, F. Thirion.....	782,809
Feed, boiler water, W. M. Lane, Sr.....	782,630
Feed mechanism, H. E. & F. L. Eberhardt.....	782,752
Feed trough, G. Shaw.....	782,440
Feed water regulator, P. B. Bastarache.....	782,281
Fire apparatus for buildings, emergency, Cotton & Larish.....	782,315
Fire escape, I. Bihl.....	782,778
Firing device, automatic, A. A. Ramsdell.....	782,539
Firearm, breech loading, G. A. Horne.....	782,260
Fireproof curtain, D. W. Adams.....	782,248
Fireproof shutter, F. C. Roberts.....	782,534
Fireproof window, E. H. Lunken.....	782,468
Fish butchering and cleaning machine, J. A. Hughlett.....	782,675
Fixture tap and receptacle holder, universal, C. S. Ryerson.....	782,249
Flexible mat, Grant & McDowell.....	782,524
Fountain, See Electrical fountain.....	782,606
Fruit picker, G. W. Merker.....	782,754
Furnace, L. De Rome.....	782,438
Furnace, Tucker & Grundell.....	782,472
Furnace, J. T. Kelly.....	782,508
Furnace door, gas, F. R. Sellman.....	782,626
Furnace spout, blast, J. T. White.....	782,298
Game board, W. Brown.....	782,594
Garment attachment, J. E. Hibline.....	782,655
Gas cut off, automatic, W. A. Michael.....	782,457
Gas generator, Thomas & Hudson.....	782,369
Gas heater, C. Eickemeyer.....	782,735
Gas, purifying illuminating, C. S. Lomax.....	782,403
Gearing, toothed, Urtel & Schilling.....	782,473
Gearing, variable speed, B. M. Coffee.....	782,547
Glass, making, W. E. Heal.....	782,394
Glazing machine, E. G. Ruder.....	782,277
Gold separating machine, Stevenson & Heft.....	782,425
Governor, explosion engine, B. W. Haydon.....	782,244
Governor, shaft, C. R. Minor.....	782,458
Grain drill, C. O. Ecker.....	782,733
Grain elevator and weigher, C. Bradford.....	782,642
Grapple, Kahler & Witham.....	782,781
Grate, movable endless, J. P. Barnes.....	782,213
Greenhouse or other structure, E. W. Hitchings.....	782,214
Grinding machine skate or tool holder, M. B. Russ.....	782,561
Guano distributor, G. W. Bowen.....	782,278
Gun, bolt, T. G. Bennett.....	782,719
Gun firing mechanism, Meigs & Jakobsson.....	782,716
Guns, control apparatus for recoiling, C. P. E. Schneider.....	782,511
Guns, means for cleaning out the bore of, F. L. Sawyer.....	782,469
Gypsum applicable for filling purposes, manufacture of crystalline, W. Brothers.....	782,701
Hair, etc., preparing, Battis & Goodell.....	782,321
Hand covering, T. J. & F. L. Seebacher.....	782,316
Hand hole covering, A. C. Lynch.....	782,583
Hand wheel, F. H. Richards.....	782,404
Harrow and seed coverer, combined, J. E. Roth.....	782,275
Harrow coupling, G. E. Blaine.....	782,360
Harvester, corn, F. B. Pierce.....	782,717
Harvester guard, W. Webber.....	782,522
Harvesting machine, corn, J. H. Johnson.....	782,296
Hat and coat hook, C. Faust.....	782,449
Hat fastener, W. W. McNaughton.....	782,738
Hat fastener, separable, W. W. McNaughton.....	782,683
Header and shredder, W. Giles.....	782,684
Header construction, J. M. McClellon.....	782,746
Heater, W. Richter.....	782,353
Heating furnace, continuous, J. Reuleaux.....	782,699
Hinge, P. M. Nelson.....	782,697
Hinge bracket, E. R. Argenbright.....	782,374
Hinge for storm windows, separable, J. Diehl.....	782,327
Hinge, release, Struble & Cain.....	782,327
Hog scalding trough, E. Scherer.....	782,428
Hook, W. M. Williams.....	782,702
Horseshoe, V. Piedilatte.....	782,302
Horseshoe calking machine, E. Rosser.....	782,693
Hose coupling, S. W. Gooch.....	782,759
Hose coupling, W. J. Bulger, Jr.....	782,555
Hose rack, S. Mellinger.....	782,595
Hose support, lawn, H. S. Parker.....	782,617
Hot air register, H. Symonds.....	782,461
Hydro-extractors, electrical drive for, W. L. D'Olier.....	782,707
Hydrocarbon furnace, G. C. Calentine.....	782,708
Hygienic and therapeutical purposes, apparatus for, J. M. A. Lacomme.....	782,646
Ice cream freezer attachment, S. M. Shoemaker.....	782,774
Indexing mechanism, B. M. W. Hanson.....	782,400
Ingot molds, gutter plate for bottom cast, W. J. Levey.....	782,584
Inhaling device, A. Goldstaub.....	782,240
Insulated rail joint, G. L. Hall.....	782,452
Insulators, arrangement for securing wires on, J. Macek.....	782,747
Internal combustion engine, Sterne & Davis.....	782,652
Jack, A. Searls.....	782,676
Jar, R. H. McCoy.....	782,471
Jar, bottle, etc., closure, G. E. Crawford, et al.....	782,421
Joint, See Angle joint.....	782,411
Jug lid, automatic, D. A. D. MacMaster.....	782,806
Knife head, C. J. Foster.....	782,577
Knitting machine, straight, A. Benndorf.....	782,330
Label applying machine, box, J. Aspen-leiter.....	782,480
Lace fastener, shoe, S. Lipkowitz.....	782,638
Lamp, T. S. Leese, reissue.....	782,673
Lamp for heating brooders, G. C. Chase.....	12,318
Lamp ignition device, central draft, C. E. Gervais.....	782,725
	782,551

Rambler

SURREY, TYPE ONE
18 horse power, \$1350

This carriage is a demonstrated, not merely a theoretical success. Five months use on the Pacific Coast shows that its upkeep is small, and that like all other Ramblers, it is to be depended upon wherever roads are fit for travel. Full information on request. Other Models \$750, \$850, \$2000 and \$3000. Immediate delivery.

THOMAS B. JEFFERY & COMPANY
Main Office and Factory, Kenosha, Wisconsin
Branches, Boston, Chicago, Philadelphia
New York Agency, 134 West Thirty-eighth Street
Representatives in all other leading cities




REMINGTON TYPEWRITER

Made in America

Has been carried to the uttermost corners of the earth:—
because of its proved ability to write the thought of the world in any language that has an alphabet.

REMINGTON TYPEWRITER COMPANY
New York and Everywhere

AMERICAN JUMP SPARK IGNITION OUTFITS



MARINE
AUTOMOBILE




STATIONARY
MOTORCYCLE



SEE CATALOGUE W.

AMERICAN COIL COMPANY, Somerville, Mass.



The Twentieth Century Polishing Lathe

occupies a floor space of only 24x30 inches, and stands 40 inches high. It is designed for light buffing and polishing required by gold and silver platers. Both shafts are made of steel and run in self-adjusted babbitted boxes with perfect alignment. Driving wheel 24 inches in diameter. The Box Top, 17x30 inches, made of finely seasoned hardwood, lined with heavy zinc. Price, with No. 2 Head, \$18.00; With No. 2 C Head, \$19.50; With No. 3 Head (as in cut), \$20.00; With 3-lap Head, \$21.00. Weight, 160 lbs.

THE W. W. OLIVER MFG. CO., 1483 Niagara Street, - BUFFALO, N. Y.



To California

In less than three days from Chicago—what an agreeable change! Why endure three more long months of winter weather, when you can leave it all and go to balmy California on a train like the

Golden State Limited

Every comfort and convenience—a gorgeous hotel on wheels, if you please—expressly for YOU. Daily via El Paso and the Southern Pacific through New Mexico. Most southerly course—quickest to reach the realm of summer. Every mile is a mile away from winter. Full information about this train and other service, to California, with booklet "The Golden State," promptly on request.

JOHN SEBASTIAN
Passenger Traffic Manager Rock Island System
CHICAGO

AGENTS

wanted in every locality to represent the Keystone Fire Extinguisher. We offer attractive inducements for permanent, profitable occupation. Previous experience not required. The

KEYSTONE

Fire Extinguisher



has been examined and approved under the standard of the National Board of Fire Underwriters. It is the CHEAPEST and BEST approved extinguisher on the market. This agency can be carried in addition to other business interests. Write to-day for full particulars.

JAMES BOYD & BROTHER
18 N. 4th St., Philadelphia
Manufacturers of
FIRE PROTECTION EQUIPMENT
Fire Hose, Hose
Couplings, Hose Pipes, etc.




One-third of a Century Standard of the World

A delicious beautifier, preserver and cleanser of the teeth; makes the breath sweet and the gums tender. The Metal Box is a handy package for the toilet table and traveling; no powder to litter; no liquid to spill or stain. 25 Cents, at all Druggists.

C. H. Strong & Co., Props., Chicago, U. S. A.

HENRY & HORA'S Modern Electricity



Explains X-Rays, Wireless Telegraphy, Radium, Transmission & Distribution Power Stations, Wiring, etc. Written in plain English.

All Problems Solved

Practical—Accurate—Scientific
150 illustrations.
355 pages. Cross index.
"A practical handbook for students, apprentices, and electrical engineers."—Scientific American.

Silk Cloth, decorative cover, silver stamping, . . . \$1.00
Seal Leather, marbled edges, gold stamping, . . . 1.50

LAIRD & LEE, PUBLISHERS CHICAGO
263 Wabash Ave.

SENSITIVE LABORATORY BALANCE.

By N. Monroe Hopkins. This "built-up" laboratory balance will weigh up to one pound and will turn with a quarter of a postage stamp. The balance can be made by any amateur skilled in the use of tools, and it will work as well as a \$125 balance. The article is accompanied by detailed working drawings showing various stages of the work. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1154. Price 10 cents. For sale by MUNN & Co., 361 Broadway, New York City, or any bookseller or newsdealer.

U. S. A. LIQUID PISTOL

Will stop the most vicious dog (or man) without permanent injury. Perfectly safe to carry without danger of leakage. Fires and recharges by pulling the trigger. Loads from any liquid. No cartridges required. Over 10 shots in one loading. All dealers, or by mail, 50c. Rubber-covered holster 5c. extra.

PARKER, STEARNS & SUTTON, 226 South St., New York

ALL THE WATER YOU WANT WITHOUT COST


Other than the first price of a machine, **NIAGARA HYDRAULIC RAM** costs less than a windmill or an engine. Requires no fuel, attention or expense. Wherever there is a running stream the Niagara will work automatically day and night. Forces water any height, any distance. Used by U. S. Government, Railroads and Factories.

Free Catalogue. **NIAGARA HYDRAULIC ENGINE CO.**
Chester, Pa.
140 Nassau St., New York

ARTESIAN
Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1500 feet. Write us stating exactly what is required and send for illustrated catalogue. Address **PIERCE WELL ENGINEERING AND SUPPLY CO.**
136 LIBERTY STREET, NEW YORK, U. S. A.

Lamp, incandescent electric, J. H. Guest..	782,749
Lamp, signal, H. W. Souder ..	782,285
Lamps, spiritus igniter for petroleum, S. Carlson ..	782,486
Lath, metal, P. Kuhne ..	782,667
Lathe, automatic screw cutting and turning, Coulter & Laws ..	782,220
Lavatory, J. Maddock ..	782,753
Leaf system leaf inserter, loose, T. W. C. Bohn ..	782,773
Level, gravity, T. F. Deck ..	782,779
Lifting jack, O. A. Dahl ..	782,326
Liquid heater, A. Waldbaur ..	782,632
Liquids with gases, apparatus for treating, R. Quarez ..	782,622
Loader, E. Bivert ..	782,772
Locomotive boiler, J. M. McClellon ..	782,362
Locomotive brake shoe, H. L. Winslow ..	782,533
Locomotive drive wheel, W. A. Taylor ..	782,623
Loom pick motion, H. Cote ..	782,777
Loom, pile fabric, Dornan & Shinn ..	782,494
Loom shedding mechanism, F. Lacey ..	782,569
Loom shuttle, automatic filling replenishing, O. Janelle ..	782,570
Low water and circulation alarm for gasoline engines, J. Schopbach ..	782,505
Lubricating machine, R. H. Elkins ..	782,703
Lubricator, G. W. Thurston ..	782,225
Lubricator, Wolcott & Davidson ..	782,532
Lubricator, W. R. Elchensner ..	782,590
Magnetic controlling mechanism, A. C. Eastwood ..	782,734
Mail box, J. E. Graham ..	782,731
Mail pouch catcher, G. W. Mershon ..	782,748
Mail receptacle, M. S. Field ..	782,512
Massage apparatus, J. C. Johansen ..	782,229
Massage implement rubber, J. Barker ..	782,663
Match, friction, F. F. Sommers, Jr. ..	782,715
Matching and gluing machine, V. T. & C. Johnson ..	782,284
Measuring apparatus, S. H. Cobb ..	782,342
Measuring device, tailor's or dressmaker's, F. Hosford ..	782,325
Metal working machines, feed stop for, B. M. W. Hanson ..	782,339
Metal working machines, screw feed mechanism for, B. M. W. Hanson ..	782,243
Metal working machines, steady rest for, B. M. W. Hanson ..	782,241
Mitten, armored, W. C. Niebuhr ..	782,238
Molding apparatus, A. K. Beckwith ..	782,517
Motion, obtaining oscillating or reciprocal, H. H. Young ..	782,538
Moving machine, J. W. Latimer ..	782,310
Music sheet guiding means, G. B. Kelly ..	782,783
Nail clipper, H. C. Hart ..	782,685
Nipper adapted to bend at right angle and to flat the ends of metal wires, E. G. Christiansen ..	782,654
Nut lock, J. W. Poince ..	782,546
Nut lock, H. K. Forbis ..	782,266
Nut lock, J. Rogers ..	782,329
Nut lock, A. C. Baumwart ..	782,418
Nut lock, A. M. Gaines ..	782,434
Nuts, bolts, studs, etc., means for locking, D. Marshall ..	782,808
Oil can, C. W. Epperson ..	782,349
Oiling device, chain wheel, K. G. Roebeling ..	782,736
Opera glass, C. F. Glocker ..	782,276
Optical projection apparatus, A. T. Thompson ..	782,553
Ore sampler, A. G. Gullberg ..	782,586
Ores or other uses, machine for crushing, D. J. Nevill ..	782,235
Oscillating engine, H. J. Uhlenkott ..	782,284
Oxygen, obtaining, G. F. Jaubert ..	782,801
Paper board apparatus, corrugated, J. N. Hahn ..	782,609
Paper board machine for making corrugated, J. N. Hahn ..	782,558
Paper board, means for making, T. W. McFarland ..	782,559
Paper, cockle straightener for coated, M. Cashin ..	782,354
Paper perforating machine, E. H. McCloud ..	782,218
Paste, mucilage, etc., receptacle or jar for, P. D. Stretch ..	782,263
Peat collector, tubular, W. A. Milne ..	782,427
Peat for fuel, preparing, Vaughan & Horner ..	782,260
Pencil and sharpener, combined, W. G. Cramer ..	782,587
Penholder, G. L. Black ..	782,726
Penholder finger hold, B. B. Goldsmith ..	782,540
Phonograph records, composition for making duplicate, J. W. Aylsworth ..	782,388
Piano tone modifying means, I. B. Smith ..	782,375
Picker. See Fruit picker ..	782,799
Pie making machine, H. L. Manning ..	782,614
Pie making machine crust molding mechanism, H. L. Manning ..	782,615
Pier, floatable concrete, Hadlock & Brown ..	782,615
Pile fabric, C. C. Golder ..	782,557
Pinion filling machine, C. J. Cleveland ..	782,745
Pipe coupling, D. E. Brockett ..	782,644
Pipe cutter, D. L. Ellis ..	782,482
Pipe cutting machine, J. Parker ..	782,226
Pitman connection, H. A. W. Smith ..	782,462
Placket holder, H. N. Northrop ..	782,424
Planter marking attachment, corn, J. F. Callahan ..	782,460
Planter, potato, G. W. Spencer ..	782,381
Planter, seed, S. A. Morris ..	782,527
Platinum contact substances, revivifying, Knietzsch & Scharff ..	782,459
Plow, W. T. Huggins ..	782,782
Plow, double shovel, A. F. Herod ..	782,658
Portable case, F. B. Hagaman ..	782,395
Postmarking and canceling machine, E. R. Malmberg ..	782,651
Power transmission device, elastic, G. H. Harris ..	782,510
Power transmitter, friction clutch, S. Borton ..	782,560
Power transmitting device for sewing or other machines, F. Petri ..	782,481
Printing press, Palmer & Denmead ..	782,692
Printing press, device for cleaning the inking rollers and ink plates of cylinder, F. Johnson ..	782,356
Profiling machine, B. M. W. Hanson ..	782,341
Pseudo-cycloidal acetone and making same, Merling & Welde ..	782,242
Pulley or wheel, L. S. Lachman ..	782,679
Pulleys, manufacture of metal, W. Livingstone ..	782,253
Pulling device, E. L. Biladeau ..	782,509
Pulp, manufacture of articles from fibrous, C. H. Valentine ..	782,378
Pump, I. O. Day ..	782,371
Pump, centrifugal, J. M. King ..	782,493
Pump, centrifugal, turbine, or like, F. Ray ..	782,343
Pump, centrifugal, turbine, or similar, F. Ray ..	782,271
Pump, metal, F. J. Wich ..	782,273
Pump, multistage centrifugal, turbine, or like, F. Ray ..	782,209
Punching implement, belt, W. W. Woodley ..	782,272
Puzzle, W. Perdue ..	782,307
Racking off and cask filling apparatus, G. W. Jackson ..	782,464
Radiators, etc., vacuum air valve for, A. E. Duram ..	782,251
Rail brace, W. S. Weston ..	782,328
Rail guard, J. Ford ..	782,588
Rail joint, C. Kofsky ..	782,443
Rail joint, O. M. Deemer ..	782,399
Rail joint splice bar lock, R. Lang ..	782,645
Railway, C. H. Howard ..	782,571
Railway frog, reversible, V. Angerer ..	782,398
Railway rail stay, E. Laas ..	782,714
Railway signal, automatic electric, W. S. Jackson ..	782,568
Railway tie, metallic, Blair & Ditchfield ..	782,751
Railway tie, steel, J. M. Griswold ..	782,317
Railway track aligning apparatus, Shaw & Eberle ..	782,389
Range or stove, hot air, S. Turansky ..	782,362
Razor box, safety, M. & A. S. Zinn ..	782,631
Receiving apparatus, H. Shoemaker ..	782,713
Rein guide, C. Mitchell ..	782,422
Road making machine, S. Randall ..	782,261
Rock drill, E. Temple ..	782,270
Roof for mausoleums, tombs, etc., O. J. Copeland ..	782,429
Rotary engine, H. N. Rathjen et al. ..	782,436
Rotary engine, M. B. Mills ..	782,359
Rotary engine, E. Uren ..	782,513

ALL THE SECRETS JIU-JITSU



THE WONDERFUL JAPANESE METHOD of attack and self-defense, by which the WEAK defeat the STRONG, in one volume, complete, by Capt. Harry H. Skinner, 12mo, cloth, nearly 100 photo-illustrations. By mail, \$1.00.

THIS BOOK is the OFFICIAL TREATISE of the System IN USE AT NEW YORK POLICE HEAD-QUARTERS and by the officers of the U. S. Army and Navy.

PRESIDENT ROOSEVELT, our most distinguished exponent of Jiu-Jitsu,

says the art is worth more in every way than all of our athletics combined.—Review of Reviews.

THE U. S. GOVERNMENT has adopted this Science as a part of the instruction at Annapolis Naval Academy and West Point Military School.

Jiu-Jitsu, by Capt. Skinner, described with simple eloquence, enriched with many photographs from life. Handsomely printed.—New York American.

Jiu-Jitsu—Capt. Skinner gives clear, careful explanations of all the various positions.—N. Y. World.

Capt. Skinner's book is a comprehensive work in letterpress and pictures of this remarkable science.—Tribune.

The reading of this book is all that is necessary to make you master of all the secrets of JIU-JITSU


JAPAN PUBLISHING COMPANY

Dept. E. American Tract Society Building, New York, N. Y.

MICROSCOPES

New Students' Compound Microscope, full outfit, - \$6.00
New Small Laboratory Microscope, full outfit, - 9.00
New Large Laboratory Microscope, full outfit, - 18.00

Instructions and complete outfit of mounting material with each microscope. Send for lists.
Dept. 6, WILLIAMS, BROWN & EARLE, 918 Chestnut St., Philadelphia, Pa.



"STANDARD" Two-Speed Automatic Coaster Brake Hub

Makes wheeling a delight, eliminates the drudgery. Do not waste money on experiments when you can buy a perfect attachment all in one hub. Our little booklet tells all about it and is mailed free. Write to-day.

STANDARD SPOKE AND NIPPLE CO. - Torrington, Conn.



"We Analyze Everything"

AT REASONABLE RATES

Should you want to know what is contained in any preparation or product, address

THE ELLSWORTH LABORATORIES

Max D. Slimmer, Ph.D.
Suite 406, Ellsworth Bldg., Chicago

ELECTRO MOTOR. SIMPLE. HOW TO

make.—By G. M. Hopkins. Description of a small electric motor devised and constructed with a view to assisting amateurs to make a motor which might be driven with advantage by a current derived from a battery, and which would have sufficient power to operate a foot lathe or any machine requiring not over one man power. With 11 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 941. Price 10 cents. To be had at this office and from all newsdealers.



Cheap Power from Kerosene

SAFE, SIMPLE, VALVELESS AND RELIABLE

Universal Kerosene Engine.

Automatic in operation, easily started, and runs steadily and at a comparatively high rate of speed at a cost of less than one pint of kerosene oil per actual horse power hour. Praised wherever used. Highest efficiency at lowest cost. For prices and terms address


UNIVERSAL KEROSENE ENGINE CO.
137 Liberty St., New York

Kerosene Oil Engine

Nothing but Kerosene Oil to run it

Simple, Safe and Efficient. Needs little attention, is less likely to get out of order, and is cheaper to run than any other engine manufactured. Economical and Easily Operated.

International Power Vehicle Co.
Stamford, Conn.



Hydro-Carbon Motors

Headless Self-Contained

It is as easily controlled as a steam engine. Variable speed.

The only perfect moderate priced launch engine on the market.

Let us convince you. Write to-day.

Grant-Ferris Co., Troy, N. Y.

Automobile and Marine Motors Simple, Compact and Powerful

Best Material. Perfect workmanship. Send for Catalog

ALEXANDER & CROUCH

40 So. Canal St., Chicago

1, 2 & 4 Cylinder, 4, 8 & 16 H. P.

HAIR

A Practical Invention That has Proven Effective

Last month we suggested to those placing order for the Evans Vacuum Cap that their checks be dated ten days in advance.

The Jefferson Bank guarantee on the Cap, however, together with the fact that nearly every sale has led to other orders, has simply deluged us with work, and we now suggest that those who con-

template placing order date their checks at least thirty days ahead, as we cannot promise earlier shipment.

This, of course, is quite a reflection upon our ability in not being prepared, but we now have arrangements under way that will enable us to make shipment of nearly a thousand Caps daily.

The Evans Vacuum Cap is used a few minutes each day, and it only requires about ten days to get the scalp loose and pliable and this condition

is essential to the life and growth of the hair—the hair cannot thrive in a tight and congested scalp.

The Vacuum gives the scalp a pleasant, tingling sensation, and the advantage of the process is that a healthful circulation is obtained without rubbing and without the use of drugs or lotions.

Illustrated book, describing this invention and its possibilities, will be sent to any one on request.

Evans Vacuum Cap Co.

425 Fullerton Building,

St. Louis, Mo.

THE MONTHLY JOURNAL

CONCRETE

An up-to-date publication devoted to the various branches of concrete construction. Send \$1.00 for a year's subscription. Sample free.
Concrete Publishing Co., 33 Congress St., W., Detroit, Mich.

The Ring or The Bank?

Now is the time to start a Diamond Savings Account


Select the Diamond you would like to own and wear from our 1905 Catalogue and it will be sent at once on approval. If you like it, pay one-fifth of the price and keep it, sending the balance to us in eight equal monthly payments. We open these accounts with all honest persons who want to save. Diamonds will pay 20 per cent profit from increased values in 1905, or five times better than banks. Satisfaction absolutely guaranteed. Write for Catalog today.

LOFTIS BROS. & CO. (Est. 1858)

DIAMONDS, WATCHES, JEWELRY

Dept. B. 180, 92 to 98 State Street, Chicago, Ill.

Winners of Gold Medal at St. Louis Exposition.



The Autocar

The Car of Simplicity

THE Autocar stands as a triumph in automobile building. Its construction combines with greatest efficiency and durability a simplicity that is the wonder of all who see it. This is a feature that commends itself alike to the novice and the expert. It means minimum liability of derangement, greatest ease and safety of operation, and lowest running expense. Each type of Autocar represents the nearest to perfection in its class. Every Autocar is built upon lines proven correct by experience; built of absolutely the best material, and with the best workmanship procurable.

Autocar records of actual performance bear out the claim that for good day-in-and-day-out, up-hill-and-down service, for durability and freedom from annoyance the Autocar is unsurpassed.

The new car, Type XI, illustrated above, shows a number of very valuable improvements, accomplishing increased ease of control, safety, and simplicity. Four cylinder vertical motor, double side entrance tonneau, \$2,000.

Type VIII, Four-passenger Car, Rear Entrance Tonneau, \$1,400, and Type X, 10 H. P. Runabout, \$900, are the cars which have made the present reputation of the Autocar, to which the new Type XI will surely add.

WRITE FOR CATALOGUE AND DEALER'S NAME

The Autocar Company

ARDMORE, PA.

Member A. I. A. M.

YOUR EYE

RIGHT HERE!

Now let us send you the Free Book telling all about it. We will also send you Prof. Sloan's fifty original suggestions for improving your handwriting.

Conklin's

SELF-FILLING PEN

"The Pen That Fills Itself"

Dip pen in any ink well or any ink, press lever and operation is over. As a matter of cleanliness, comfort and convenience don't you owe it to yourself to learn more about this perfect pen? If you will let us send you our beautiful new illustrated catalogue, it will make you a CONKLIN enthusiast.

The Conklin Pen Co. 126 Madison Ave. Toledo, Ohio

Represented in Great Britain by American Agencies, Ltd., 38 Shoe Lane, Farringdon St., London, E. C. In Australia by Rae, Munn & Gilbert, 47 Market St., Melbourne.

Sad iron, J. M. Harper	782,501
Safety hook, F. Dronne	782,603
Sandpapering machine, G. Herrmann	782,245
Sandpapering machine, H. W. Rugg	782,798
Sash lock, T. E. Smith	782,764
Sash lock, lift, and support, F. Neudorff	782,412
Saw, J. L. Hiers	782,396
Saw tooth tool, T. Olsen	782,690
Scow, C. Kuhn	782,567
Seal, F. W. Brooks	782,435
Seal, bottle, C. Ingulli	782,601
Searchlight mounting, Webber & McGeorge	782,297
Separator bundle straightener, J. W. Alsop	782,317
Separator screen, P. L. Simpson	782,283
Sewing machine bobbin case latch, E. L. Bowers	782,541
Sewing machine thread holder and cutter, E. M. Campbell	782,543
Shade hanger, window, D. Campbell	782,484
Shade supporting bracket, U. G. Rich	782,698
Shaping machine guard, T. L. Harris	782,392
Sheet metal plates, cutting ends from, J. Lee	782,451
Shirt bosom retainer, E. H. Fifield	782,385
Shoestring having removable ornaments, C. A. Funk	782,604
Shower pipe, W. H. Millspaugh	782,755
Shutter bower and fastener, S. E. Brown	782,721
Sign, advertising, C. R., Sr., C. R., Jr., & L. C. Groff	782,498
Signal, See Car or train signal	782,760
Sink trap attachment, A. Savard	782,292
Slicer, vegetable or fruit, W. & F. Walter	782,445
Slipper, fabric, J. H. Giles	782,288
Speaking tube, W. J. Storey	782,535
Spinning frame bobbin holder, A. Ashworth	782,228
Spinning ring, T. P. Farmer	782,236
Spiral cutting machine, B. M. W. Hanson	782,503
Spool holder, E. Hechheimer	782,433
Spoon, temperature indicating, H. E. Ashley	782,531
Sprinkler system, automatic, E. L. Thompson	782,262
Sprocket wheel, cone, F. L. Morse	782,406
Squeezer, Mayhew & Hilderhof	782,256
Stake holder, Lewis & Bostwick	782,373
Stalk cutter, G. W. Whitcomb	782,608
Stanchion, cattle, C. H. Knickerbocker	782,475
Steam boiler, S. S. Lanyon	782,331
Steam engine, J. S. Wignall, Jr.	782,393
Steam trap, P. Fraser	782,519
Step and seat, folding, C. N. Hazelton	782,303
Stereoscope, C. L. Pappenhausen	782,515
Sterilizing apparatus, Winchel & Whaley	782,351
Stone base, artificial, C. C. McElhaney	782,230
Stone block, artificial, M. Q. Mullenix	782,711
Stone building blocks, mold for making artificial, J. Finger	782,694
Stopper extractor, W. H. Wheeler	782,607
Storage apparatus, C. Piez	782,334
Stove, coal and gas, Massett & Black	782,358
Stove, hot air blast, Gunn & Mulloy	782,672
Stove water back, D. F. Printz	782,332
Strainer, milk, J. O. Linden	782,529
Striking bag and swivel and universal joint attachments therefor, H. & E. J. Goldsmith	782,723
Switch stand, semaphore, A. A. Strom	782,800
Syringe, hypodermic, M. Campbell	782,254
Syringe, hypodermic, F. W. Steuer	782,382
Telephone relay, J. W. Larish	782,562
Telephone exchange system, W. M. Davis	782,419
Telephone register, M. Hitt	782,323
Telephone switch, intercommunicating, W. H. Rose	782,376
Telephone system, D. W. Campbell	782,600
Telephone system, four party line, G. Babcock	782,453
Teneriffe lace wheel, R. E. Dexter	782,363
Thermometer, J. I. Linler	782,447
Threshing machine, J. H. Sommer	782,483
Tile, corner, E. Hazlehurst	782,379
Tiles, production of undercut, W. H. Cammeyer	782,703
Tire, rubber, C. H. Bryan	782,318
Tire shrinker, J. G. Shuster	782,219
Tire, vehicle, S. G. Board	782,466
Tobacco cartridge, W. E. Coleman	782,291
Tool head and fastening device therefor, C. F. Rabb	782,605
Tool holding apparatus, E. L. Truman	782,696
Totalizing mechanism, H. E. Goldberg	782,312
Track sander, A. B. Potts	782,544
Traction apparatus, electric, A. Zehden	782,405
Tray, R. J. Carrier	782,589
Trolley, J. Martland	782,756
Trolley, B. Williams	782,786
Trolley guard, E. R. Nord	782,796
Trolley pole controller, J. P. Magney	782,650
Trolley switch, A. Palmros	782,601
Trousers shaper, J. Greenleaf	782,682
Truck and frame, combined railway car, W. H. Didlake	782,582
Truck attachment, hand, H. L. Myers	782,671
Trumpet, carriage, W. F. Schmeltz	782,700
Trunk, L. Lieberman	782,222
Tumbling barrel, J. R. Rusby	12,317
Turbine, Cuthbert & Snyder	782,267
Turbine, compound steam, H. F. Fullagar, reissue	782,623
Turbine, steam, W. L. Pope	782,536
Turbine, steam, Bateau & Sautter	782,549
Type machine adjusting or centering mechanism, J. S. Bancroft	782,775
Type machine die case transposing mechanism, J. M. Dove, et al.	782,635
Type setting and distributing machine, L. S. Campbell	782,542
Typewriter, G. W. Winters	782,357
Typewriting machine, L. S. Burridge	782,744
Umbrella carrier, C. C. Pogue	782,212
Umbrella, folding, C. P. Funk	782,730
Umbrella gear, Baldwin & Treman	782,689
Umbrella rib, Fretz & Yeagley	782,520
Valve, J. J. Dunwoody	782,634
Vegetable cutter, D. J. O'Keefe	782,465
Vehicle, E. Pearl	782,518
Vehicle antirattler, Wilcox & Hickok	782,591
Vehicle wheel, E. L. Perry	782,691
Vehicle wheel, G. S. Ogilvie	782,258
Vehicles, power installation for self-propelled, P. H. Batten	782,720
Vending apparatus, automatic, R. E. Payne	782,294
Vending machine, W. M. Mack	782,348
Vessel, packing, C. M. Brown	782,441
Wagon brake, J. M. Webb	782,709
Wagon, dumping, W. S. Livengood	782,574
Wall construction, J. A. Ferguson	782,521
Warp beam, C. Taubert	782,496
Washing machine, H. Lindstrom	782,390
Watch protector, E. V. Phillips	782,688
Water column, N. P. Fenner, Jr.	782,525
Water flood gate, J. Hansen	782,765
Water gage, J. O'Connor	782,338
Water heater, electrical, M. H. Shoenberg	782,481
Water tube boiler, superheating, J. P. Sneddon	782,320
Weighing machine, automatic, G. J. Hicks	782,233
Well system, oil, F. J. Moser	782,279
Well underreamer, J. J. Brewster	782,336
Wells, inducing a flow of oil from oil, B. F. Gardner	782,727
Wheel, See Hand wheel	782,767
Wheel, F. Saxon	782,442
Wheel, P. F. Hein	782,718
Wheel, R. S. Cutter	782,743
Wheel, J. G. Stewart	782,729
Whip operating device, W. Fahrney	782,578
Whip supporter, J. D. Flanagan	782,771
Whips in sockets, means for locking, P. Bolre	782,585
Window, I. Fischer	782,366
Window closing device, W. S. Doe	782,252
Window lock, T. Padgett	782,274
Window screen, metal, S. W. Benson	782,572
Wire clamp and tightening device, J. M. Sweet	782,592
Wires, supporting bracket for messenger, H. D. Stroud	
Wood filler, S. D. Kudysch	
Wrench, J. C. Reisinger	
Wrench, W. H. Leister	
Wrench, M. W. Brady	

DESIGNS.

Advertising label, W. J. Dietrich	37,332
Bottle, C. W. Meinecke	37,336



In ancient times the coach and four—in modern times the

OLDSMOBILE

Emerson complained that railways had robbed travel of its sentiment and pleasure. The sage of Concord had never ridden in an Oldsmobile, which combines the speed of the train with all the delights of stage coach travel, revives the sentiment and pleasure with all the discomforts left out.

The Oldsmobile Touring Car with its graceful lines and abundance of power yields instant obedience to the touch of the driver and unites comfort with wonderful speed and endurance. Its 20 H. P. two-cylinder motor meets every requirement with entire freedom from the complications of the four-cylinder cars. Inexpensive to operate. Tire expense reduced to the lowest point. Speed from 6 to 40 miles an hour.

Oldsmobile Standard Runabout,	\$650	Oldsmobile Touring Car,	\$1400
Oldsmobile Touring Runabout,	\$750	Oldsmobile Light Delivery Car,	\$1000
Oldsmobile Light Tonneau Car,	\$950	Oldsmobile Heavy Delivery Car,	\$2000


Detailed specifications sent on request. A pack of Automobile playing cards (standard 25c. quality) postpaid for 10 cents. Address Dept. 21.

OLDS MOTOR WORKS, - DETROIT, U. S. A.

Member of Association of Licensed Automobile Manufacturers

Drawing by Edward Penfield
Copyright 1903, Brownell & Humphrey

It is an Acknowledged Fact that



Fisk "Heavy Car" Type Tire

HAS NO EQUAL

The treads are made separately and can be replaced at a small cost. The wearing surface is specially made for durability. The cushion feature is found in no other tire. The fastening is the time-tried bolt and nut principle, made rust-proof and scientifically applied. It can't roll, creep or blow off the rim, but can be removed with ease. If you are not convinced, get a booklet, or see it at our nearest branch.

THE FISK RUBBER CO., Chicopee Falls, Mass.

EASTERN SALES OFFICE
754 Seventh Ave.,
New York

WESTERN OFFICE
1251 Michigan Ave.,
Chicago, Ill.

BRANCHES: BOSTON, 226 Columbus Ave.; SPRINGFIELD, 40 Dwight St.; PHILADELPHIA, 838 Arch St.; ATLANTA, 103 N. Pryor St.; SYRACUSE, 423 So. Clinton St.; BUFFALO, 838 Main St.; CLEVELAND, 318 Euclid Ave.; DETROIT, 254 Jefferson Ave.; ST. LOUIS, 3908 Olive St.; OMAHA, 1116 Farnum St.; KANSAS CITY, 1330 Main St.; MINNEAPOLIS, 704 Hennepin Ave.; DENVER, 1534 Glenarm St.; SAN FRANCISCO, 114 Second St.; LOS ANGELES, 1034 So. Main St.

MONTREAL, CANADA.


LONDON, ENGLAND.

Safe Investments

No government security nor high grade railroad bond will yield as great a return for the money actually invested as a savings account in "The Bank that Pays 4%." And when the high standing and large capital and surplus of the institution are taken into consideration together with the character and integrity of the officers and trustees, it will be seen that no securities have a better foundation or afford greater safety.

\$1.00 or more starts an account. Booklet telling how to bank by mail sent free if you mention this paper.

Peoples Savings Bank
Pittsburgh, Pa.



DURABILITY

Fox Typewriter

On account of its perfected and superior mechanical construction a Fox will outlast any other typewriter. Repairs cost practically nothing, an important feature enjoyed by the Fox alone.

Write for particulars concerning our free trial plan, and also our 1905 catalogue just out.

Old machines taken in part payment, and easy terms given.

We want dealers for unoccupied territory. Write for our liberal proposition.

FOX TYPEWRITER CO.

Executive Office and Factory

826-840 Front St. Grand Rapids, Mich.

THE FRANKLIN MODEL SHOP

Inventors, amateur machinists, schools and colleges furnished with anything in metal from a single piece to a complete working model. Drawings and designs worked out from inventors' ideas. Write for estimates. Send for booklet No. 9, free.

PARSELL & WEED, 129-181 W. 81st St., New York

WRITING IN SIGHT

TIME SAVED by UNDERWOOD SYSTEM.

Stop losing 15 minutes of each hour lifting a heavy carriage

The UNDERWOOD SAVES TIME

Try It You Will Be Convinced.

UNDERWOOD TYPEWRITER CO
241 BROADWAY
NEW YORK

50 Years' Experience

PATENTS

Trade Marks, Designs, Copyrights, Etc.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents. Patents taken through MUNN & Co. receive Special Notice, without charge, in the

Scientific American

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.

MUNN & CO. 361 Broadway, New York
Branch Office 625 F St. Washington, D.C.

Brush, C. E. Thompson	37,340
Cabinet, kitchen, A. V. Doubt	37,342
Glass, plate, T. Woodward	37,346
Pencil tip, lead, B. B. Goldsmith	37,335
Plate or dish, W. A. Pickard	37,337
Plate server, O. T. Cushman	37,338
Register or ventilator top plate, H. S. Hart	37,345
Sign, cigar, J. I. Comber	37,333
Sleigh, C. R. Knapp	37,347
Smoking set, L. Goodman	37,334
Stand, G. J. Taylor	37,343
Stove, F. Fieberger	37,344
Type, font of, G. L. Marsh	37,348
Work table, J. B. Zink	37,341

TRADE MARKS.

Buttons, L. H. Hirsch & Co.	44,169
Cement, gypsum, and lime, Liebold & Co.	44,201
Chocolate and candy, T. H. Auerbach	44,174
Cigars and all-tobacco cigarettes, Fitzpatrick & Draper	44,175
Clothing, certain named, E. Schaeffer	44,164
Concrete building blocks, machine for making, Cement Machinery Co.	44,186
Condition powders, J. C. Zurlieh	44,187
Cotton piece goods, Carlowitz & Co.	44,181
Coupons, trading, J. H. Reolhar	44,165
Crackers, biscuits, and cakes, Crescent Macaroni Co.	44,161
Cutlery, certain named, National Cutlery Co.	44,172
Dry goods, certain named, Burton Bros. & Co.	44,192
Eggs, fresh, C. B. Stephan	44,163
Food products, certain, Peninsula Produce Exchange of Maryland	44,173
Hosiery, R. J. Fisher	44,170
Insecticides, Omnia Chemical Co.	44,167
Linings, M. W. Burd	44,182
Lockets and emblems, Thornton Brothers	44,166
Macaroni, spaghetti, vermicelli, and noodles, Anger Baking Co.	44,162
Medicated soap, certain named proprietary, World's Dispensary Medical Association	44,197
Medicine for topical application, X-Zalia Corporation	44,179
Oil, cotton seed, Gulfport Cotton Oil, Fertilizer & Mfg. Co.	44,194
Oil, lubricating engine, Galena Signal Oil Co.	44,200
Pencils, American Lead Pencil Co.	44,199
Powder, antiseptic, Vreeland Chemical Co.	44,184
Powder, talc, National Toilet Co.	44,195
Remedy for certain named diseases, F. A. Thomas	44,176
Remedy for piles, South African Remedy for Piles Syndicate	44,180
Rubber boots, shoes, and galoshes, Ostasische Handels-Gesellschaft	44,196
Scouring powder, Reitz Stone Co.	44,188
Skimmers, M. M. Argersinger	44,177
Soap, certain named, J. A. Simonds	44,193
Spoons, forks, and knives, E. H. H. Smith Silver Co.	44,178
Stone building blocks, machines for making artificial, Harmon S. Palmer Hollow Concrete Building Block Co.	44,191
Tetter cure, J. J. Hooper & Sons	44,185
Washing fluid, M. F. Tobianski	44,183
Waterproofed cloth, Fulton Bag and Cotton Mills	44,198
Worsted and cotton piece goods, Farr Alpaca Co.	44,189

LABELS.

"Absorbine," for veterinary remedy, W. F. Young	11,875
"Ammo," for washing powder, F. L. Fraser	11,868
"Battle Royal," for cigars, Moeller & Kolb	11,863
"Buster Brown Transfer-o-s," for transfer paper, Paas Dye Co.	11,878
"Certified Check," for cigars, George A. Kent Co.	11,862
"Cleamsil Cream," for face cream, R. V. Valley	11,871
"Dixie," for beer, Lexington Brewing Co.	11,867
"Dr. Edmur's Antiseptic Barb Wire Liniment," for liniment, Edmur Pharmacal Co.	11,874
"Dur Adorno Paint," for paint, A. Hendrich	11,876
"For Dessert Tap-po," for a food preparation, Fruit Pudding Co.	11,858
"Gingerette," for ginger brandy, Power & Stalter	11,866
"Horse Shoe Brand," for harness leather, Federal Oak Leather Co.	11,879
"Ideal Sanative Cold Cream," for cold cream, W. B. Shaw	11,872
"In Case of Accident or Emergency," for emergency supplies in case of accident, J. B. Daymont	11,877
"Ingersoll Cream Cheese," for cheese, C. C. L. Wilson	11,860
"Jersey Cream Soda Water," for soda water, B. H. McDonald	11,861
"John Alden Brand," for canned goods, foods, and relishes, Driscoll, Church & Hall	11,857
"Killkoff," for cough medicine, F. A. Richter, Jr.	11,869
"License Stamp," for garters, Nealon Company	11,882
"Lowney Chocolate," for chocolate bonbons, Walter M. Lowney Co.	11,855
"Orange Blossom," for bacon, C. Stoppenbach's Sons	11,859
"Pompeian Massage Cream and Skin Food," massage cream, Pompeian Mfg. Co.	11,873
"Seal Back," for cigars, Grill Bros. Co.	11,864
"Sokol Bro's Tea Best Russian Quality," for tea, J. Sokol	11,865
"Supreme Brand," for oranges, F. H. Keeler & Co.	11,854
"Swiss Herb Life Essence," for medicine, C. Forster	11,870
"The Melba," for hose supporters, Carson, Pirie, Scott & Co.	11,881
"Tibbetts Blue Point Soup," for soup, N. V. Tibbetts	11,856
"Zilko," for mercerized crochet cotton, Carson, Pirie, Scott & Co.	11,880

PRINTS.

"A Wheel Tinder Box," for matches, Diamond Match Co.	1,206
"Ales," for beers and ales, Kaufmann & Strauss Co.	1,202
"Breaking up a Cold," for medicine, D. Weeks	1,204
"Congress Cards make players happy," for playing cards, United States Playing Card Co.	1,212
"Flint Lock Tinder Pistol," for matches, Diamond Match Co.	1,207
"Lucifers," for matches, Diamond Match Co.	1,211
"Official," for catarrh remedy, W. S. Woodruff	1,205
"Owl Cigar," for cigars, Seifer & Kappes	1,203
"The First Match," for matches, Diamond Match Co.	1,208
"The Match of 1805," for matches, Diamond Match Co.	1,210
"The Paint Educator," for paint, Pimbley Paint and Glass Co.	1,213
"The Perfect Match," for matches, Diamond Match Co.	1,209

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

THE HARRINGTON & KING PERFORATING CO.
PERFORATED METAL OF EVERY DESCRIPTION.
FOR ALL USES.
223 NO. UNION ST. CHICAGO, ILL.

SPECIAL MANUFACTURING.
DIES AND STAMPINGS TO ORDER.
SPEC'L MACHINERY—MODELS—EXPERIMENTAL WORK.
DROP FORGING DIES AND DROP FORGINGS.
HARDWARE SPECIALTIES ETC. MANFD TO ORDER. SEND SAMPLES OR DRAWINGS FOR ESTIMATES. WRITE FOR OUR BOOKLET.
THE GLOBE MACHINE & STAMPING CO.
970 HAMILTON ST., CLEVELAND, OHIO.

ICE MACHINES. Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 809 Clinton St., Milwaukee, Wis.

MODELS & GEARS. CATALOGUE FREE. UNION MODEL WORKS 193 CLARK CHICAGO.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. E. V. BILLARD, Fox Bldg., Franklin Square, New York.

The Loomis Automobile & Marine Specialties Known the world over for efficiency and durability. Carburetors, Mufflers and Circulating Pumps. LOOMIS AUTOCAR CO., Westfield, Mass., U. S. A.

BALLOONS Aeronaut L. Stevens, Box 181 Madison Sq., N. Y.

PATENT AND WORKING DRAWINGS. G. M. MAYER, M.E., Monadnock Bld., Chicago, Ill.

CHEMICAL EXAMINATIONS OF ALL KINDS. DR. H. C. STIEFEL, Bissell Block, Pittsburgh, Pa.

THE SCHWERTLE STAMP CO. STEEL STAMPS, LETTERS & FIGURES. BRIDGEPORT, CONN.

Experimental & Model Work Ctr. & advice free. Wm. Gardam & Son, 45-51 Rose St., N.Y.

INSTRUMENTS OF PRECISION HIGH GRADE MACHINERY Inventions Perfected

PHILIP A. GEIER, 50 High St., Cleveland, O.

Manufacturers **HARDWARE SPECIALTIES** Contract Manufacturers and will market articles of merit. LARIMER MFG. CO., 155 S. Jefferson St., Chicago

NOVELTIES & PATENTED ARTICLES MANUFACTURED BY CONTRACT. PUNCHING DIES, SPECIAL MACHINERY. E. KONIGSLOW, STAMPING & TOOL WORKS, CLEVELAND, O.

WELL DRILLING and PROSPECTING MACHINES. For Water, Oil, Gas, Coal, Etc. LOOMIS DRILL CO., TIFFIN, Ohio.


Magical Apparatus. Grand Book Catalogue. Over 700 engravings 25c. Parlor Tricks Catalogue, free.

MARTINKA & CO., Mfrs., 493 Sixth Ave., New York.

Telegraphy Circular free. Wonderful automatic teacher. 5 styles \$2 up. OMNIGRAPH CO., Dept. 62, 59 Cortlandt St., New York.

The Finsen Light Treatment FOR SKIN DISEASES

has proven eminently successful in America. We have permanently relieved many serious cases at our Institute by our Genuine High Power Finsen Lamps imported from Copenhagen. This treatment is not a cure-all, but it is sure in many diseases heretofore regarded as incurable, as Lupus (skin consumption), Eczema, Psoriasis, Skin Cancer, Birthmarks and Facial Blemishes. It is knifeless, painless, harmless. We have special books describing each of the above and other skin diseases in detail and giving names of cured patients. They are free. Write for the book you desire.



PROF. NIELS R. FINSEN

THE FINSEN LIGHT INSTITUTE OF AMERICA
Suite D, 78 State St., Chicago

EXPERT DIE MAKERS AND MACHINISTS

Moulds, Models, Experimental Work INSTRUMENT MAKING and SMALL MACHINERY THOS. H. HART & CO., Charlestown, Mass.

NAME PLATES—STEEL STAMPS "EMPLOYEE CHECKS, KEY TAGS & BADGES" J. ROBBINS MFG. CO. 58 KNEELAND ST. SEND FOR CATALOGUE BOSTON, MASS.

MASON'S NEW PAT. WHIP HOIST for Outrigger hoists. Faster than Elevators, and hoists direct from teams. Saves handling at less expense. Manfd. by VOLNEY W. MASON & CO., Inc. Providence, R. I., U. S. A.

TYPEWRITERS ALL MAKES All the Standard machines SOLD or RENTED ANYWHERE at HALF MANUFACTURERS' PRICES. Shipped with privilege of examination. Send for Cat. Typewriter Emporium, 203 LaSalle St., Chicago

"Raffles"

Gentleman Burglar

The activity of the Scotland Yard detectives forces "Raffles," gentleman burglar, to temporary retirement—"a rest cure," he calls it.

He breaks into the house of the Inspector of Prisons, who is traveling on the Continent. Here "Raffles" makes his home.

The Inspector returns unexpectedly and upsets the Crackman's plans. He overcomes, gags, and binds the unlucky official, and leaves him to take "a rest cure" of a rather indefinite length.


"The Rest Cure," the third "Raffles" tale, appears in

Now on sale

Collier's

Ten cents the copy

MARCH HOUSEHOLD NUMBER



Orient Surrey, Price \$450


FOR 4 PASSENGERS, -- \$450

Nothing on earth can duplicate this as a motor-car proposition. Better than ever, this year—simplified carburetor, improved muffler, almost noiseless driving pinions, larger spring surface, and a new, patented, starting device that lets the engine turn so easily a child can start it.

Half-an-hour's instruction—then out on the road—a fast, light, dependable car that will fairly eat up the hills.

Write for the Orient Style Book, showing nine Air-Cooled Orions from \$375 to \$2,250. Free if you address Dept. 4.

WALTHAM, MFG. CO., - Waltham, Mass.
Members of Association of Licensed Automobile Manufacturers



CHARTER

Stationaries, Portables, Hoisters, Pumps, Sawing and Boat Outfits, Combined with Dynamos.

Gasoline, Gas, Kerosene.

Send for Catalogue.

State Power Needs.

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.


What Is Daus' Tip-Top?



TO PROVE that Daus' "Tip-Top" is the best and simplest device for making 100 copies from pen-written and 50 copies from typewritten original, we will ship complete duplicator, cap size, without deposit, on ten (10) days' trial. Price \$7.50 less \$5 Net trade discount of 33 1/3 per cent, or

The Felix A. B. Daus Duplicator Co., Daus Bldg., 111 John St., New York

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

HOROLOGICAL DEPARTMENT
BRADLEY POLYTECHNIC INSTITUTE

Formerly Parsons Horological Institute
PEORIA, ILLINOIS

LARGEST and BEST

WATCH SCHOOL in AMERICA

We teach Watch Work, Jewelry, Engraving, Clock Work, Optics. Tuition reasonable. Board and rooms near school at moderate rates.
Send for Catalog of Information.

Photo Lenses

and Shutters of every

kind for all purposes;

Professional,

Amateur, Process.

Sold Round the World on all

Cameras. Catalogue free.

Bausch & Lomb Opt.

ROCHESTER, N. Y.

New York Chicago Boston

2d Military
Information Division
Chief of Staff
War Dept


CRUDE ASBESTOS
DIRECT FROM MINES

PREPARED ASBESTOS FIBRE for Manufacturers use
R. H. MARTIN,
OFFICE, ST. PAUL BUILDING
220 B'way, New York.

MAGIC LANTERNS

PAY BIG Stereoscopic and Moving Picture Machines. Public Exhibitions PAY BIG. Small capital required. Views and Films illustrating any subject. Catalogue free. Magic Lanterns for Home Amusement. McAllister, 49 Nassau St., New York.

The Wizard Engine



With Pump

OLDS ENGINES

Economical Power

In sending out their last specifications for gasoline engines for West Point, the U. S. War Department required them "to be Olds Engines or equal." This speaks volumes for our engines. It means they excel all others or the U. S. Government would not demand them.

They are the horizontal type, 2 to 100 H. P., and are so simply and perfectly made that it requires no experience to run them, and Repairs Practically Cost Nothing.

Send for a catalogue of our Wizard Engine, 2 to 8 H. P. (spark ignition system, same as in the famous Oldsmobile), the most economical small power engine made; fitted with either pump-jack or direct connected pump; or our general catalogue showing all sizes.

Olds Gasoline Engine Works, Lansing, Mich.

New York Agents, R. H. Drvo & Co., Binghamton, N. Y.

JESSOP'S STEEL THE VERY BEST FOR TOOLS, SAWS, ETC.
WM JESSOP & SONS, 12 31 JOHN ST. NEW YORK

WE WANT TO GIVE YOU THIS
\$1.00 LIGHTNING CALCULATOR FREE

The greatest labor-saving work on figures ever published.

ABSOLUTELY INVALUABLE to merchants, mechanics, manufacturers, bankers, machinists, clerks or anyone who handles figures. No matter what the example is, it shows the whole answer at a glance. No limit to how large or small the figures, or what the fraction. Every conceivable problem fully worked out and answer given at once.

THE GREATEST BOOK of its kind the world has ever known. The answer to any question is as easily found as a word in a pocket dictionary.

This Book required 35 years' work to complete it. No matter who you are or what your business, this book prevents mistakes, relieves the mind, saves labor, time and money, makes you independent, sure and self-reliant in figures.

WE GIVE IT TO YOU FREE ON THESE TERMS

We want to increase the Subscription List to our Monthly Journal,

MODERN MACHINERY. The foundation of civilization rests on inventions of new machinery. To keep abreast of mechanical progress should be the aim of every intelligent man. Our publication keeps you informed, and it is written so all can understand it, and the best illustrated of its class. **MODERN MACHINERY costs you \$1.00 a year.** We want to get you started reading this paper regularly, and therefore make you this offer.

MODERN MACHINERY, ONE YEAR, ROPPS NEW CALCULATOR (JUST OUT) PUBLISHER'S PRICE, \$1.00 } \$2.00 Value

Send us your subscription at once, enclosing \$1.00 with this ad., and we will mail you **Modern Machinery** every month for one year and the **Calculator FREE** at once. If not just as represented, send the book right back and we will refund your money. Don't delay accepting this proposition; write to-day. Remember, money back to-morrow if dissatisfied.

MODERN MACHINERY PUB. CO., 813 Security Bldg., CHICAGO, ILL.

New England WATCHES

The man who owns or drives an Auto should not use an expensive watch. The New England screw cased watches are perfection for motor work.

Dust and wet proof. Accuracy guaranteed

THE NEW ENGLAND WATCH CO., 37 & 39 Maiden Lane, New York
63 Victoria Street, Liverpool, England

LANTERN SLIDES? The Largest Stock of Fine Slides.

Artistic, Historic and Popular. Includes every subject, Scientific, Professional, and every best projecting lantern made. Send for full information, stating subjects.
WILLIAM H. RAU, 1322 CHESTNUT ST., PHILADELPHIA, PA.

"The most satisfactory cement Mill made."



THE GRIFFIN MILLS which we have sold for this purpose will produce 50,000 barrels of Portland cement a day, or over 15,000,000 barrels a year. No other mill approaches such a record, because no other mills begin to work as cheaply or as satisfactorily. Write for our illustrated descriptive catalogue.

BRADLEY PULVERIZER CO. BOSTON. NEW YORK. CHICAGO.

Self-inking, requires no dipping. WILL RULE BACKWARD OR FORWARD.

Will rule any kind of paper. Will not leak or drop ink. Made of hard rubber, with metal wheel holder.

Every line will be uniform its entire length, not broad and heavy in one place and light and indistinct in another.

Ink Pads are interchangeable so that any wheel can be used with any pad you have in stock.

THE BAGBY PEN CO., Sole Manufacturers, Dept. J, 177 La Salle St., Chicago, Ill.

BAGBY RULING PEN

ALWAYS READY FOR USE




With additional wheels (obtained at a slight extra cost) a great variety of rulings and borders may be produced.

We have special pens for draughtsmen, architects, accountants and bookkeepers. Please specify the kind desired when writing.

Every Accountant, Engineer, Draughtsman, Book keeper, wants one, and it is universally being used by Colleges and Schools.

Price, One Dollar, Prepaid


Factory Motors



Furnished for every kind of manufactures. Efficient and always reliable.

Frames in single casting. Machines constructed for wall, floor, or ceiling, and easily rearranged for any position. Every individual part of the best material and most skilled make, the chief end sought being efficiency and speed. Shafts of the best grade open-hearth steel. Bearings of phosphor bronze, self-oiling and self-aligning. Each machine fully guaranteed.

ROCHESTER ELECTRIC MOTOR CO.
10-12 Frank St., Buffalo, N. Y., U. S. A.



Every Gas Engine User should learn about the Apple Automatic Spark. Easily attached. No more belt, battery or commutator troubles. Increases power and speeds. For any kind of ignition apparatus write

The Dayton Electrical Mfg. Co., 88 Beaver Bldg., Dayton, Ohio.

By wearing the kind that moves when you do—that's **PRESIDENT Suspenders**. You can't feel them; long wearers—smart lookers. 50c any store or mailed. The C. A. Edgarton Mfg. Co., Box 310, Shirley, Mass.



GARDNER'S STOCK
C. H. BISHOP & CO. CHICAGO, ILL. U.S.A.
15 to 21 Clinton Street.